

SUMMARY OF QUANTITIES CONTINUED

ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FED. / 20% STATE			100% STATE			0021		
				0003 ROADWAY	0003 DETOUR ROUTE	0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178	0040 BOX CULVERTS	BOX CULVERTS TO BE CLEANED	BAUER ROAD 80% Federal 10% State 10% County	OLD RIVER RD 80% Federal 20% State	LATHAM ROAD 80% Federal 10% State 10% County	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	25		25							
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,086	1,086								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	159	159								
40600300	AGGREGATE (PRIME COAT)	TON	436	436								
40600895	CONSTRUCTING TEST STRIP	EACH	3	3								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	132.5	132.5								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	196	196								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	15,334	15,334								
40701931	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/2"	SQ YD	119,022	119,022								
40702700	FURNISH PROFILOGRAPH	L SUM	1	1								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	780	780								
42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	1,955	1,955								
42000410	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2"	SQ YD	3,083	3,083								
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	533	533								
42001300	PROTECTIVE COAT	SQ YD	16,410	16,410								
44000100	PAVEMENT REMOVAL	SQ YD	55,366	55,366								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	387	387								
44000400	GUTTER REMOVAL	FOOT	2,233	2,233								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	37	37								
44002228	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7"	SQ YD	501	501								
44003100	MEDIAN REMOVAL	SQ FT	28,942	28,942								
44004250	PAVED SHOULDER REMOVAL	SQ YD	4,597	4,597								
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,454	3,454								
48100100	AGGREGATE SHOULDERS, TYPE A	TON	7,040	7,040								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	601		601							
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	197	197								
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	52,610	52,610								
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	6,443	6,443								
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1								
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1								
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1								
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1								
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1								
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1								
50105220	PIPE CULVERT REMOVAL	FOOT	104	104								
50200100	STRUCTURE EXCAVATION	CU YD	632		632							
50300225	CONCRETE STRUCTURES	CU YD	91.7	11.7		80						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	401.4			401.4						
50300260	BRIDGE DECK GROOVING	SQ YD	954			954						
50300300	PROTECTIVE COAT	SQ YD	1,194			1,194						
50400735	FURNISHING AND ERECTING PRECAST, PRESTRESSED CONCRETE BUILT T-BEAMS 63"	FOOT	1,559			1,559						

I:\projects\11254\segment_1\sheet\sheet11\mrc\254sum81.dgn

Rev.