SUMMARY OF QUANTITIES CONTINUED

	ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0003 ROADWAY	80% FED./20% STATE 0003 DETOUR ROUTE	0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178	0040 BOX CULVERTS	100% STATE BOX CULVERTS TO BE CLEANED	0021 BAUER ROAD 80% Federal 10% State 10% County	0021 OLD RIVER RD 80% Federal 20% State	0021 LATHAM ROAD 80% Federal 10% State 10% County
•	63301000	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL	FOOT	87.5	87.5							
•	63500105	DELINEATORS	EACH	136	136							
	64200105	SHOULDER RUMBLE STRIPS	FOOT	40,335	40,335							
•	66201120	CONCRETE SHOULDER CURB	FOOT	40	40							
	66400105	CHAIN LINK FENCE, 4'	FOOT	2029	2029							
	66406100	CHAIN LINK GATES, 4' X 18' DOUBLE	EACH	2	2							
	66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	248	248							
	66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	6	6							
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24							
	67100100	MOBILIZATION	L SUM	1	1							
	70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1							
	70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1							
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5						
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1							
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1							
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1							
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90							
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	22	22							
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	287		287						
	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	515	515							
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	138,842	138,842							
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	426	426							
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	902	902							
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	30,555	30,459	96						
	70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	587.5	587.5							
	70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	3	3							
	70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2							
*	72000100	SIGN PANEL - TYPE 1	SQ FT	858	780					27	27	24
*	72000200	SIGN PANEL - TYPE 2	SQ FT	292	292							
*	73000100	WOOD SIGN SUPPORT	FOOT	2,178	2,178							
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	719		719						
•	78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	9,019	9,019							
•	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	2046	2046							
•	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	123,450	123,450							
•	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	17,540	17,540							
•	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	5409	5409							
•	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	883	883							
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	714	714							
•	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	5							
•	78200410	GUARDRAIL MARKERS, TYPE A	EACH	25	25							
•	78200520	BARRIER WALL MARKERS, TYPE B	EACH	8			8					
•	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7							

* Specialty Items

USER NAME = thompsrd	DESIGNED RDT/GC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN RDT	REVISED -	
PLOT SCALE = 50.0000 FT / IN.	CHECKED GC	REVISED -	
PLOT DATE = 2/3/2011	DATE 01-14-11	REVISED -	

ILLINOIS ROUTE 2
SUMMARY OF QUANTITIES - 5

SCALE: N.T.S. | SHEET NO. 10 OF 530 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	77-2-2 & 77-2B-1	WINNEBAGO	530	10

CONTRACT NO. 64813

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

I:\projects\1254\segment 1\sheets\civil\misc\254csum01.dgn