

SUMMARY OF QUANTITIES CONTINUED

ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FED./20% STATE				100% STATE BOX CULVERTS TO BE CLEANED	0021		
				0003 ROADWAY	0003 DETOUR ROUTE	0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178	0040 BOX CULVERTS		BAUER ROAD 80% Federal 10% State 10% County	OLD RIVER RD 80% Federal 20% State	LATHAM ROAD 80% Federal 10% State 10% County
78300100	PAVEMENT MARKING REMOVAL	SQ FT	15,423	15,423							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	60	60							
* X8040102	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	3						1	1	1
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	162						20	56	86
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	17						4	5	8
81400710	HEAVY-DUTY HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1								1
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3						1	1	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,078						1,758	1,904	2416
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	162						20	56	86
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12						4	4	4
X8250505	LIGHTING CONTROLER SPECIAL	EACH	3						1	1	1
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	3	3							
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	3						1	1	1
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	2						1		1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	8,795						2174	2244	4377
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	8,863						3390	2710	2763
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	184						28	43	113
87502470	TRAFFIC SIGNAL POST, GALVANIZED STEEL 13 FT.	EACH	1								1
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	9						2	4	3
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1						1		
87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	4						2	2	
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1						1		
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	2								2
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	3							1	2
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1							1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	33						6	12	15
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	9						3	3	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	184						58	66	60
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21							21	
87900200	DRILL EXISTING HANDHOLE	EACH	4						4		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5							1	4
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	27						8	8	11
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	10						4	4	2
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	27						10	8	9
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	37						12	12	13
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1						1		
89502380	REMOVE EXISTING HANDHOLE	EACH	3						3		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4						4		
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1								1
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	83	83							

\*Specialty Items

I:\projects\11254\segment\_1\sheet\civil\mso\254sum01.dgn

USER NAME = thompsd	DESIGNED RDT/GC	REVISED -
PLOT SCALE = 50,000 FT / IN.	DRAWN RDT	REVISED -
PLOT DATE = 2/3/2011	CHECKED GC	REVISED -
	DATE 01-14-11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 2 SUMMARY OF QUANTITIES - 6		
SCALE: N.T.S.	SHEET NO. 11 OF 530 SHEETS	STA. TO STA.

F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 11
CONTRACT NO. 64813				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				