

SUMMARY OF QUANTITIES CONTINUED

| ITEM # | ITEM DESCRIPTION | UNIT | URBAN TOTAL QUANTITY | 001.FED./201.STATE | | | | | 100%.STATE BOX CULVERTS TO BE CLEANED | 0021 BAUER ROAD 80% Federal 10% State 10% County | 0021 OLD RIVER RD 80% Federal 20% State | 0021 LATHAM ROAD 80% Federal 10% State 10% County |
|----------|---------------------------------------------------------------------------------------------------------------|----------|----------------------------|--------------------|-------------------------|---------------------------------------------------------------|-------------------------|---------------------------|------------------------------------------------|--------------------------------------------------------------|-----------------------------------------------------|---------------------------------------------------------------|
| | | | | 0003 ROADWAY | 0003 DETOUR ROUTE | 0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178 | 0040 BOX CULVERTS | 0003 TOTAL QUANTITY | | | | |
| B2000562 | TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| B2001262 | TREE, CORNUS ALTERNIFOLIA (PAGODA DOG WOOD), 4' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| B2001664 | TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| B2002614 | TREE, MALUS ADAMS (ADAMS CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| B2005214 | TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| C2012836 | SHRUB, VIBURNUM TRILOBUM (AMERICAN CRANBERRY VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED | EACH | 100 | 100 | | | | | | | | |
| D2001772 | EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED | EACH | 50 | 50 | | | | | | | | |
| X0300249 | REMOVE EXISTING GATE | EACH | 5 | 5 | | | | | | | | |
| X0322118 | REMOVE CONCRETE FLARED END SECTIONS | EACH | 2 | 2 | | | | | | | | |
| X0322352 | SEEDING MOBILIZATION | EACH | 10 | 10 | | | | | | | | |
| X0322533 | REMOVE EXISTING MAST ARM ASSEMBLY AND POLE | EACH | 3 | | | | | | 3 | | | |
| X0322654 | GRADE AND SHAPE MEDIAN DITCH CHECKS | EACH | 99 | 99 | | | | | | | | |
| X0323256 | REMOVE AND RELOCATE FLAGPOLE | EACH | 1 | 1 | | | | | | | | |
| X0324855 | SLOPED METAL END SECTIONS WITH GRATE, 36" | EACH | 4 | 4 | | | | | | | | |
| X0325206 | RELOCATE INTERCONNECT CABLE | FOOT | 15 | | | | | | 15 | | | |
| X0325358 | SLOPED METAL END SECTIONS WITH GRATE, 30" | EACH | 2 | 2 | | | | | | | | |
| X0326711 | VIDEO CAMERA CONTROL SYSTEM | L SUM | 1 | | | | | | 0.3 | 0.4 | 0.3 | |
| X0488100 | REMOVING EXISTING SEPTIC TANK | EACH | 3 | 3 | | | | | | | | |
| X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 500 | | | 500 | | | | | | |
| X4060310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, SPECIAL | TON | 591 | | 591 | | | | | | | |
| X4400110 | TEMPORARY PAVEMENT REMOVAL | SQ YD | 675.3 | 675.3 | | | | | | | | |
| X4402810 | ISLAND SURFACE REMOVAL AND REPLACEMENT | SQ FT | 628 | | | | | | 628 | | | |
| X5121800 | PERMANENT STEEL SHEET PILING | SQ FT | 9,160 | | | 9,160 | | | | | | |
| X6061460 | PAVED DITCH (SPECIAL) | FOOT | 770 | 770 | | | | | | | | |
| X6062700 | CONCRETE GUTTER, TYPE A (SPECIAL) | FOOT | 810 | 810 | | | | | | | | |
| X6063600 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 | FOOT | 4899 | 4899 | | | | | | | | |
| X6064201 | COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06 | FOOT | 925.5 | 925.5 | | | | | | | | |
| X7010216 | TRAFFIC CONTROL AND PROTECTION SPECIAL, LOCATION 1 | LUMP SUM | 1 | 1 | | | | | | | | |
| X8950305 | REMOVE EXISTING SIGNAL HEAD | EACH | 13 | | | | | | 13 | | | |
| XX003163 | EMERGENCY VEHICLE PRIORITY SYSTEM | EACH | 3 | | | | | | 1 | 1 | 1 | |
| Z0001062 | DRAIN FOR AGGREGATE BASE COURSE | SQ YD | 141 | 141 | | | | | | | | |
| Z0005300 | BOX CULVERTS TO BE CLEANED | EACH | 1 | | | | | 1 | | | | |
| Z0005400 | BREAKER-RUN CRUSHED STONE | TON | 995 | 995 | | | | | | | | |
| Z0007603 | BUILDING REMOVAL NO. 3 | L SUM | 1 | 1 | | | | | | | | |
| Z0007605 | BUILDING REMOVAL NO. 5 | L SUM | 1 | 1 | | | | | | | | |
| Z0007606 | BUILDING REMOVAL NO. 6 | L SUM | 1 | 1 | | | | | | | | |
| Z0007607 | BUILDING REMOVAL NO. 7 | L SUM | 1 | 1 | | | | | | | | |
| Z0007608 | BUILDING REMOVAL NO. 8 | L SUM | 1 | 1 | | | | | | | | |
| Z0007609 | BUILDING REMOVAL NO. 9 | L SUM | 1 | 1 | | | | | | | | |

100% BAUER RD. (WINNEBAGO CO.)
100% LATHAM RD. (WINNEBAGO CO.)
100% OLD RIVER RD. (NORTHWEST
FIRE PROTECTION DIST.)

* Specialty Items

I:\projects\11254\segment_1\sheet\civil\mase\254\sum8.dgn

Rev.