

EARTHWORK SCHEDULE - IL 2

LOCATION		20200100 EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25% CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	ROCK EXCAVATION, WEATHERED CU YD	ROCK EXCAVATION, WEATHERED ADJUSTED FOR SWELL 15% CU YD	ROCK EXCAVATION, SOLID CU YD	ROCK EXCAVATION, SOLID ADJUSTED FOR SWELL 15% CU YD	20201200 REMOVAL AND DISPOSAL OF UNSATURABLE MATERIAL CU YD	2000226 QUARRY RUN GRANULAR EMBANKMENT CU YD	21101625 TOPSOIL FURNISH AND PLACE, 6-INCHES SQ YD	21101645 TOPSOIL FURNISH AND PLACE, 12-INCHES SQ YD	25000100 SEEDING, CLASS 1 ACRE	25400201 SELECTIVE MOWING STAKES EACH	
ILLINOIS ROUTE 2	ELMWOOD	695+00	755	566	-2	564						833			3	
	695+00	700+00	5,633	4,225	-78	4,147						2,656			3	
	700+00	705+00	679	509	-4	505						1,022			3	
	705+00	710+00	1,822	1,367	-35	1,332							2,000	0.01	6	
	710+00	715+00	5,333	4,000	-930	3,070						2,778	3,478	0.18	10	
	715+00	720+00	3,215	2,411	-10,555	-8,144						8,933		0.26	10	
	720+00	725+00	15,980	11,985	-5,150	6,835						3,606	4,144	0.02	10	
	725+00	730+00	44,840	33,630	-176	33,454							12,278	0.33	10	
	730+00	735+00	40,832	30,624	-29	30,595							10,639	0.40	10	
	735+00	740+00	33,848	25,386	-532	24,854							10,211	0.42	4	
	740+00	742+00	956	717	-26,369	-25,652					13,659	12,063	3,800	0.14	4	
	744+00	745+00	117	88	-9,069	-8,981					10,050	11,678	3,700	0.13	4	
	745+00	750+00	17,315	12,986	-30,920	-17,934					27,813	32,830	9,467	2,372	0.39	10
	750+00	755+00	65,739	49,304		49,304							12,250	0.40	15	
	755+00	760+00	22,211	16,658	-46	16,612							5,622	5,178	0.44	10
	760+00	765+00	17,611	13,208	-5,605	7,603							11,333	0.06	4	
	765+00	770+00	15,170	11,378	-6,582	4,796							14,689	0.17	5	
	770+00	775+00	2,813	2,110	-8,307	-6,197							11,467	0.33	10	
	775+00	780+00	7,894	5,921	-5,221	700						7,744	3,722	0.36	10	
	780+00	785+00	2,697	2,023	-12,344	-10,321							12,678	0.41	10	
	785+00	790+00	8,554	6,416	-12,874	-6,459							12,722	0.42	10	
	790+00	795+00	5,407	4,055	-12,332	-8,277							11,256	0.39	10	
	795+00	800+00	3,392	2,544	-10,535	-7,991							9,467	0.42	10	
	800+00	805+00	26,041	19,531	-2,131	17,400							1,956	7,161	0.31	10
	805+00	810+00	29,759	22,319	-393	21,926							4,556	7,194	0.42	10
810+00	815+00	25,469	19,102	-241	18,861	367	422	348	400			9,594	0.18	10		
815+00	820+00	17,922	13,442	-2,815	10,627	913	1,050	754	867			6,528	0.18	6		
820+00	825+00	2,700	2,025	-22,117	-20,092							11,533	0.32	10		
825+00	830+00	3,104	2,328	-18,017	-15,689							11,456	0.48	10		
830+00	835+00	3,373	2,530	-16,597	-14,067							13,289	0.35	10		
835+00	840+00	11,931	8,948	-2,116	6,832							13,950	0.39	10		
840+00	845+00	33,385	25,039	-2	25,037								9,411	0.22	10	
845+00	850+00	8,396	6,297	-581	5,716								6,317	0.16	10	
850+00	855+00	3,542	2,657	-614	2,043							4,222	0.01	5		
TEMPORARY CROSSOVER		6,891	5,168	-940	4,228											
SUB-TOTAL		495,326	371,495	-224,259	147,236	1,280	1,472	1,102	1,267	51,522	56,570	210,856	96,356	8.68	282	
OLD RIVER RD. STAGE 1	1346+00	1351+00	702	527		527						489			6	
	1351+00	1355+00	1,275	956	-4	952						467			3	
	SUB-TOTAL		1,977	1,483	-4	1,479							956			
OLD RIVER RD. STAGE 2 AND 2A	1342+00	1344+00	1,386	1,040	-4,279	-3,240						2,767			0	
	1346+00	1351+00	1,697	1,273	-1,114	159						1,522			6	
	1351+00	1355+00	405	304	-981	-677						744			3	
	SUB-TOTAL		3,488	2,616	-6,374	-3,758							5,033			9
CASTLE DRIVE	300+11	305+00	473	355	-2,896	-2,541						1,545			8	
	305+00	311+02	1,621	1,216	-4,404	-3,188						3,844			10	
	SUB-TOTAL		2,094	1,571	-7,300	-5,730							5,389			
BAUER PKWY	995+50	999+30	6,909	5,182	-24	5,158									6	
	SUB-TOTAL		6,909	5,182	-24	5,158							2,600			
LATHAM ROAD	STAGE 1															
	1646+62	1650+00	1,336	1,002	-93	909						1,589			6	
	1650+00	1655+00	4,612	3,459	-110	3,349						3,656			10	
	1655+00	1660+00	3,765	2,824	-657	2,167						3,622			10	
	1660+00	1665+00	7,395	5,546	-1,264	4,282						3,856			0	
	1665+00	1670+00	30,691	23,018		23,018						6,278			8	
	1670+00	1674+00	11,761	8,821	-1,196	7,625	489	562	543	624		2,878			4	
	STAGE 1 SUBTOTAL															
	STAGE 2															
	1674+00	1680+00	568	426	-12,572	-12,146	22					4,522			10	
	1680+00	1685+00	781	586	-10,678	-10,092						4,078			6	
	1685+00	1690+00	872	654	-7,328	-6,674						4,156			10	
	1690+00	1695+00	2,502	1,877	-1,911	-35						3,678			10	
	1695+00	1700+53	3,054	2,291	-1,276	1,015						2,111			10	
	STAGE 2 SUBTOTAL		7,777	5,833	-33,765	-27,932	22	26				18,544				
SUB-TOTAL		67,337	50,503	-37,085	13,418	511	588	543	624			40,422			84	

I:\projects\11284\Segment 1\Sheet 15\Drawings\25400201\25400201.dgn

USFR NAME = ehorepard	DESIGNED RDT/GC	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 2 SCHEDULE OF QUANTITIES - 2			F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 16
PLOT SCALE = 50,000 FT / IN.	DRAWN RDT	REVISED		SCALE: N.T.S.	SHEET NO. 16 OF 530 SHEETS	STA. TO STA.	CONTRACT NO. 64813				
PLOT DATE = 4/7/2011	CHECKED GC	REVISED		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							