

63100085 - TRAFFIC BARRIER TERMINAL, TYPE 6

LOCATION	QTY (EACH)
IL ROUTE 2 NORTHBOUND	
742+03.71 LT.	1
742+03.71 RT.	1
SOUTHBOUND	
743+59.71 LT.	1
743+59.71 RT.	1

TRAFFIC BARRIER TERMINAL, TYPE 6, TOTAL = 4 EACH

63100167 - TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

LOCATION	QTY (EACH)
IL ROUTE 2 NORTHBOUND	
738+03.76 LT.	1
738+03.76 RT.	1
834+20.88 RT.	1
854+69.95 RT.	1
SOUTHBOUND	
747+02.71 LT.	1
747+02.71 RT.	1
840+71.14 LT.	1

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT), TOTAL = 7 EACH

63301000 - REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL

LOCATION	LENGTH (FOOT)
FRONTAGE ROAD D	
1120+05.5 TO 1120+93.0 RT.	87.5

REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TOTAL = 87.5 FOOT

\* INCLUDES EXISTING TERMINAL SECTIONS.

63200310 - GUARDRAIL REMOVAL

LOCATION	LENGTH (FOOT)
STA. 719+56 RT. TO STA. 721+61 RT., 176' RT.	203
STA. 720+53 RT. TO STA. 721+59 RT., 118' RT.	106
STA. 1028+20 RT. TO STA. 1029+96 RT.	177
STA. 1028+52 LT. TO STA. 1030+09.68 LT.	158
STA. 1030+09.68 LT. TO STA. 1030+16 LT.	6
STA. 1030+43 RT. TO STA. 1031+02 RT.	60
STA. 1030+68 LT. TO STA. 1031+22 LT.	54
STA. 743+28, 170' RT. TO STA. 748+68, 169' RT.	540
STA. 743+39, 137' RT. TO STA. 749+14, 135' RT.	575
STA. 1106+49 LT. TO STA. 1107+31.22 LT.	82
STA. 1107+31.22 LT. TO STA. 1107+50 LT.	19
STA. 1106+82 RT. TO STA. 1107+31.22 RT.	68
STA. 1107+31.22 LT. TO STA. 1107+50 LT.	12
STA. 1120+05 LT. TO STA. 1121+12 LT.	107
STA. 1126+61 LT. TO STA. 1127+38 LT.	78
STA. 807+93 RT. TO STA. 808+94 RT.	100
STA. 836+71 RT. TO STA. 837+74 RT, 125' RT.	103
STA. 836+77 RT. TO STA. 837+80 RT, 155' RT.	103
STA. 854+71 RT. TO STA. 855+75 RT.	100

GUARDRAIL REMOVAL, TOTAL = 2,651 FOOT

66400105 - CHAIN LINK FENCE, 4'

LOCATION	(FOOT)
723+90, 150' LT TO 736+00, 150' LT (IL ROUTE 2)	1,220
736+18, 150' LT TO 744+24, 169.85' LT (IL ROUTE 2)	809

CHAIN LINK FENCE, 4', TOTAL = 2,029 FOOT

66600105 - FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

LOCATION	EACH
691+51.00 TO 696+15.00 LT.	1
696+15.00 TO 711+50.00 LT.	21
711+50.00 TO 726+50.00 LT.	8
711+50.00 TO 726+50.00 RT.	19
726+50.00 TO 741+50.00 LT.	5
726+50.00 TO 741+50.00 RT.	14
741+50.00 TO 756+50.00 LT.	8
756+50.00 TO 771+00.00 LT.	14
756+50.00 TO 771+00.00 RT.	7
771+00.00 TO 785+50.00 LT.	7
785+50.00 TO 800+50.00 LT.	5
785+50.00 TO 800+50.00 RT.	7
800+50.00 TO 815+00.00 LT.	6
800+50.00 TO 815+00.00 RT.	6
815+00.00 TO 829+50.00 LT.	4
815+00.00 TO 829+50.00 RT.	5
829+50.00 TO 844+25.00 LT.	4
829+50.00 TO 844+25.00 RT.	1
844+25.00 TO 855+00.00 RT.	22
CASTLE DRIVE	4
OLD RIVER ROAD	
LATHAM ROAD	
1646+00.00 TO 1654+00.00 LT.	3
1646+00.00 TO 1654+00.00 RT.	4
1654+00.00 TO 1668+50.00 LT.	8
1654+00.00 TO 1668+50.00 RT.	7
1668+50.00 TO 1680+00.00 LT.	2
1668+50.00 TO 1680+00.00 RT.	1
1680+00.00 TO 1694+00.00 LT.	10
1680+00.00 TO 1694+00.00 RT.	9
1694+00.00 TO 1700+00.00 LT.	1
1694+00.00 TO 1700+00.00 RT.	5
FR D	15
FR E	15

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS, TOTAL = 248 EACH

70500100 - TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A

LOCATION	LENGTH (FOOT)
SB CROSSOVER	
4016+37.50 TO 4017+00 LT.	62.5
IL ROUTE 2 NORTHBOUND	
739+43.30 TO 742+03.80 LT.	262.5
739+43.30 TO 742+03.80 RT.	262.5

TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A, 587.5 FOOT

70500615 - TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1

LOCATION	QTY (EACH)
SB CROSSOVER	
4016+37.50 LT.	1
IL ROUTE 2 NORTHBOUND	
739+43.30 LT.	1
739+43.30 RT.	1

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, TOTAL = 3 EACH

70500665 - TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6

LOCATION	QTY (EACH)
IL ROUTE 2, NORTHBOUND	
742+03.80 LT.	1
742+03.80 RT.	1

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6, TOTAL = 2 EACH

66406100 - CHAIN LINK GATES, 4' x 18' DOUBLE

LOCATION	(EACH)
736+00, 140' LT (IL ROUTE 2) *	1
1347+09, 147' LT (OLD RIVER ROAD)	1

CHAIN LINK GATES, 4' x 18' DOUBLE, TOTAL = 2 EACH

\* EXACT LOCATION WILL BE DETERMINED IN THE FIELD

TEMPORARY PAVEMENT MARKING

STAGE	LOCATION	WHITE (FOOT)	YELLOW (FOOT)	SYMBOLS (SQ. FT.)	
				4" WHITE (FOOT)	8" WHITE (FOOT)
STAGE 1	684+75.00 TO 711+50.00	1,822	4,478		
	711+50.00 TO 724+00.00	1,248	1,248		
	BAUER PARKWAY		859	424	
SUBTOTAL STAGE 1		3,070	6,585	424	
STAGE 2	IL ROUTE 2				
	684+75.00 TO 696+25.00	3,392	547		93.6
	696+25.00 TO 711+50.00	2,259	4,398		177
	711+50.00 TO 726+50.00	3,000	3,000		
	726+50.00 TO 741+50.00	3,000	3,000		
	741+50.00 TO 756+50.00	3,000	3,000		
	756+50.00 TO 771+00.00	3,559	2,900		46.8
	771+00.00 TO 785+50.00	2,900	2,900		
	785+50.00 TO 800+50.00	3,000	3,000		
	800+50.00 TO 815+50.00	3,026	3,662		15.6
	815+50.00 TO 830+50.00	3,000	2,808	284	93.6
	830+50.00 TO 845+50.00	3,000	3,000		
845+50.00 TO 855+80.00	2,060	2,060			
CASTLE DR		111			
LATHAM RD	264	462		46.8	
OLD RIVER ROAD	3,065	2,704			
SUBTOTAL STAGE 2	38,525	37,552	284	177	
OLD RIVER ROAD	2,736	4,094			
SUBTOTAL STAGE 2A	2,736	4,094			
SUBTOTAL		92,562	284	601	
ADD 50% FOR RESTRIPING		46,281	142	301	
TOTAL		138,842	426	902	

ITEM	QTY	UNIT
70300210 - TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	515	SQFT
70300220 - TEMPORARY PAVEMENT MARKING, LINE 4"	138,842	FOOT
70300250 - TEMPORARY PAVEMENT MARKING, LINE 8"	426	FOOT
70300260 - TEMPORARY PAVEMENT MARKING, LINE 12"	902	FOOT

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL

STAGE	LOCATION	(SQ FT)
STAGE 1	684+75.00 TO 711+50.00	2,100
	711+50.00 TO 724+00.00	832
	1014+00 (BAUER) TO 1010+43 (BAUER)	710
SUBTOTAL STAGE 1		3,267
STAGE 2	IL ROUTE 2	
	684+75.00 TO 696+25.00	1,407
	696+25.00 TO 711+50.00	2,443
	711+50.00 TO 726+50.00	2,000
	726+50.00 TO 741+50.00	2,000
	741+50.00 TO 756+50.00	2,000
	756+50.00 TO 771+00.00	2,200
	771+00.00 TO 785+50.00	1,933
	785+50.00 TO 800+50.00	2,000
	800+50.00 TO 815+50.00	2,245
	815+50.00 TO 830+50.00	2,219
	830+50.00 TO 845+50.00	2,000
845+50.00 TO 855+80.00	1,373	
CASTLE DR	37	
LATHAM RD	242	
OLD RIVER ROAD	1,923	
SUBTOTAL STAGE 2	24,916	
OLD RIVER ROAD	2,277	
SUBTOTAL STAGE 2A	2,277	
TOTAL	30,459	

DETOUR QUANTITIES

CODE	PAY ITEM	QUANTITY	UNIT
X4060310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 50, SPECIAL	591	TON
48101200	AGGREGATE SHOULDERS, TYPE B	601	TON
40200100	AGGREGATE SURFACE COURSE, TYPE A	25	TON
70300100	SHORT TERM PAVEMENT MARKING REMOVAL	96	SQ FT
78000110	PAINT PAVEMENT MARKING - LINE 4"	719	FOOT
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD T01201	1	LUMP SUM

78200410 - GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
IL ROUTE 2 NORTHBOUND	
738+53.71 TO 742+03.71 LT.	5
739+03.77 TO 742+03.71 RT.	5
SOUTHBOUND	
744+02.71 TO 747+52.71 LT.	5
744+02.71 TO 747+02.71 RT.	5
837+10.00 TO 840+10.00 LT.	5

GUARDRAIL MARKERS, TYPE A, TOTAL = 25 EACH

78200520 - BARRIER WALL MARKERS, TYPE B

LOCATION	EACH
IL ROUTE 2	
742+46.71 TO 743+59.71 LT.	4
742+46.71 TO 743+59.71 RT.	4

BARRIER WALL MARKERS, TYPE B, TOTAL = 8 EACH

78201000 - TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH
IL ROUTE 2 NORTHBOUND	
738+03.76 LT.	1
738+03.76 RT.	1
834+20.88 RT.	1
854+69.95 RT.	1
SOUTHBOUND	
747+02.71 LT.	1
747+02.71 RT.	1
840+71.14 LT.	1

TERMINAL MARKERS - DIRECT APPLIED, TOTAL = 7 EACH

78300200 - RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL

LOCATION	(EACH)
STA. 693+31 TO STA. 713+30 ROUTE 2 (SB)	25
ELMWOOD TO STA. 713+30 ROUTE 2 (NB)	35

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL, TOTAL = 60 EACH

66700305 - PERMANENT SURVEY MARKERS, TYPE II

LOCATION	EACH
(IL RTE 2) *	5
1648+60, 37.5' LT (LATHAM)	1

PERMANENT SURVEY MARKERS, TYPE II, TOTAL = 6 EACH

\* EXACT LOCATION WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.

C:\projects\1128A\Schedule of Quantities\1128A\Schedule of Quantities\1128A\Schedule of Quantities.dgn