



**LEGEND:**

- |  |                           |  |                                  |
|--|---------------------------|--|----------------------------------|
|  | PAVEMENT REMOVAL          |  | GUTTER REMOVAL                   |
|  | DRIVEWAY PAVEMENT REMOVAL |  | 12" TREE REMOVAL (UNIT DIAMETER) |
|  | SHOULDER REMOVAL          |  | CHAINLINK FENCE REMOVAL          |
|  | TREE REMOVAL, ACRES       |  |                                  |
|  | BUILDING REMOVAL          |  |                                  |
- 
- EXISTING UTILITIES LEGEND**
- |  |                              |
|--|------------------------------|
|  | UNDERGROUND TELEPHONE LINE   |
|  | UNDERGROUND FIBER OPTIC LINE |
|  | UNDERGROUND GAS LINE         |
|  | AERIAL LINE                  |

**EXISTING PLAN AND REMOVAL NOTES**

ADDITIONAL REMOVALS SHOWN IN THE DRAINAGE PLANS, SIGNAL PLANS.

ALL FENCE MATERIAL OTHER THAN CHAIN LINK WILL BE INCLUDED IN CLEARING.

BITUMINOUS DRIVEWAYS ON AGGREGATE BASE COURSE REMOVAL WILL BE INCLUDED IN EARTH EXCAVATION.

ANY HOT-MIX ASPHALT PAVEMENT REMOVAL WHICH IS LESS THAN 6" IN THICKNESS WILL BE PART OF EARTH EXCAVATION.

MAILBOX LOCATIONS WILL BE UPDATED BASED ON DISTRICT 2 STANDARDS (SEE GENERAL NOTES).

I:\projects\125\Management\1\binet\civil\amv\eh\0294810-rt\rae-m\21.dgn  
 11/15/2011 10:50:00 AM

USER NAME = zulkowd	DESIGNED STS/GC	REVISED -
DRAWN RDT	REVISIONS	REVISED -
CHECKED GC	REVISIONS	REVISED -
DATE 01-14-11	REVISIONS	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

ILLINOIS ROUTE 2 EXISTING PLAN AND REMOVALS 4 STA 726+50 TO 741+50	
SCALE: 1"=50'	SHEET NO. 55 OF 530 SHEETS
STA.	TO STA.

F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 55
CONTRACT NO. 64813				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				