



LEGEND:

- | | | | |
|--|---------------------------|----------------------------------|----------------------------------|
| | PAVEMENT REMOVAL | | GUTTER REMOVAL |
| | DRIVEWAY PAVEMENT REMOVAL | | 12" TREE REMOVAL (UNIT DIAMETER) |
| | SHOULDER REMOVAL | | CHAINLINK FENCE REMOVAL |
| | TREE REMOVAL, ACRES | EXISTING UTILITIES LEGEND | |
| | BUILDING REMOVAL | | UNDERGROUND TELEPHONE LINE |
| | | | UNDERGROUND FIBER OPTIC LINE |
| | | | UNDERGROUND GAS LINE |
| | | | AERIAL LINE |

EXISTING PLAN AND REMOVAL NOTES

ADDITIONAL REMOVALS SHOWN IN THE DRAINAGE PLANS, SIGNAL PLANS.

ALL FENCE MATERIAL OTHER THAN CHAIN LINK WILL BE INCLUDED IN CLEARING.

BITUMINOUS DRIVEWAYS ON AGGREGATE BASE COURSE REMOVAL WILL BE INCLUDED IN EARTH EXCAVATION.

ANY HOT-MIX ASPHALT PAVEMENT REMOVAL WHICH IS LESS THAN 6" IN THICKNESS WILL BE PART OF EARTH EXCAVATION.

MAILBOX LOCATIONS WILL BE UPDATED BASED ON DISTRICT 2 STANDARDS (SEE GENERAL NOTES).

USER NAME = zulkowsd	DESIGNED STS/GC	REVISED -
	DRAWN RDT	REVISED -
PLOT SCALE = 50.0001 FT / IN.	CHECKED GC	REVISED -
PLOT DATE = 2/2/2011	DATE 01-14-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ILLINOIS ROUTE 2 EXISTING PLAN AND REMOVALS 16 LATHAM RD STA 1654+00 TO STA 1668+50	
SCALE: 1"=50'	SHEET NO. 67 OF 530 SHEETS STA. TO STA.

F.A.P. RTE. 734	SECTION 77-2-2 & 77-2B-1	COUNTY WINNEBAGO	TOTAL SHEETS 530	SHEET NO. 67
CONTRACT NO. 64813			ILLINOIS FED. AID PROJECT	

I:\projects\11754\segment_11\sheet\civil\winnebago\11754-16.dgn