



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 8, 2011

SUBJECT: FAP Route 303 (IL 173)
Project NHF-0303 (053)
Section 129K-1
Winnebago County
Contract No. 64987
Item No. 218, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iv of the Table of Contents to the Special Provisions.
3. Added page 174 to the Special Provisions.
4. Revised sheets 1, 2, 4, 9 - 13, 48, 56, 59, 63, 70, 226, 227, 257 - 266, 268, 329-331 & 380 - 382 of the Plans.
5. Added sheets 268A - 268E to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Eric Therkildsen, Region 2, District 2; Mike Renner
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000114	T-ACERX FREM AB 1-3/4	EACH	15.000				
A2001714	T-ACER SACR 1-3/4	EACH	20.000				
A2006714	T-QUERCUS MACR 1-3/4	EACH	9.000				
B2002614	T-MALUS ADAM TF 1-3/4	EACH	15.000				
B2004814	T-MALUS SAR TF 1-3/4	EACH	17.000				
XZ127900	RETAINING WALL REMOV	FOOT	1,450.000				
X0322936	REMOV EX FLAR END SEC	EACH	3.000				
* X0324102	EM VEH SIGNL CONT SYS	EACH	1.000				
X0327068	PAVT COLOR & TEXTURE SPL	SQ YD	2,321.000				
X4201000	HES PCC PVT 9 1/2 J	SQ YD	1,238.000				
X4400110	TEMP PAVT REMOVAL	SQ YD	28,315.000				
X4402805	ISLAND REMOVAL	SQ FT	4,333.000				
X4404000	PARKING LOT PAVT REM	SQ YD	2,654.000				
X5610006	DI WT MNF MJ 8X6 HTEE	EACH	1.000				
X5610700	WATER MAIN REMOVAL	FOOT	125.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X5610748	WM LINE STOP 8	EACH	1.000				
X6022820	MAN SAN 5 DIA T1F CL	EACH	1.000				
X6024246	INLETS SPL N3	EACH	5.000				
X6024250	INLETS SPL N5	EACH	58.000				
X6024254	INLETS SPL N7	EACH	1.000				
X6024256	INLETS SPL N8	EACH	1.000				
X6026050	SANITARY MANHOLE ADJ	EACH	8.000				
X6026051	SAN MAN RECONST	EACH	3.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7200105	SIGN PANEL T1 SPL	SQ FT	150.000				
X7200205	SIGN PANEL T2 SPL	SQ FT	52.000				
X8050095	SERV INSTALL SPL	EACH	4.000				
X8250505	LIGHT CONTROLLER SPL	EACH	4.000				
X8410102	TEMP LIGHTING SYSTEM	L SUM	1.000				
X8750005	TS POST 14 SPL	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8770125	S C MAA&P 28 SPL	EACH	1.000				
X8770134	S C MAA&P 34 SPL	EACH	1.000				
X8770136	S C MAA&P 36 SPL	EACH	1.000				
X8770142	S C MAA&P 50 SPL	EACH	1.000				
X8770151	S C MAA&P 55 SPL	EACH	5.000				
X8770152	S C MAA&P 52 SPL	EACH	2.000				
X8770154	S C MAA&P 54 SPL	EACH	1.000				
X8770156	S C MAA&P 56 SPL	EACH	1.000				
X8770158	S C MAA&P 58 SPL	EACH	1.000				
X8770168	S C MAA&P 68 SPL	EACH	1.000				
X8770240	S C MAA&P DMA 28&55SP	EACH	1.000				
Z0005300	BOX CUL TO BE CLEANED	EACH	1.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0007603	BLDG REMOV NO 3	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0013302	SEGMENT CONC BLK WALL	SQ FT	9,452.500				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0014700	CULVERT TO BE CLEANED	EACH	3.000				
* Z0019500	DRYWELL	EACH	1.000				
Z0022800	FENCE REMOVAL	FOOT	252.000				
Z0024476	FLEX DELINEATOR MAINT	EACH	8.000				
Z0025500	F & I PROPERTY MARKER	EACH	88.000				
Z0026346	NIGHT WORK ZONE LIGHT	L SUM	1.000				
Z0026407	TEMP SHT PILING	SQ FT	1,521.000				
Z0028415	GEOTECHNICAL REINF	SQ YD	81,692.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	2.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	3.000				
Z0030280	IMP ATTN TEMP SUN TL3	EACH	3.000				
Z0030330	IMP ATTN REL FRD TL3	EACH	5.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030370	IMP ATTN REL SUN TL3	EACH	10.000				
Z0033072	VIDEO VEH DET SYS	EACH	4.000				
Z0056648	SS 1 WAT MN 12	FOOT	248.000				
Z0056668	SS 2 WAT MN 12	FOOT	93.000				
Z0056672	SS 2 WAT MN 24	FOOT	103.000				
Z0062456	TEMP PAVEMENT	SQ YD	28,977.000				
Z0065753	SLOT DR 15" W/6" SLOT	FOOT	30.000				
Z0073002	TEMP SOIL RETEN SYSTM	SQ FT	1,376.000				
Z0077700	WOOD FENCE REM & RE-E	FOOT	292.000				
20100110	TREE REMOV 6-15	UNIT	765.000				
20100210	TREE REMOV OVER 15	UNIT	287.000				
20101100	TREE TRUNK PROTECTION	EACH	36.000				
20200100	EARTH EXCAVATION	CU YD	45,079.000				
20201200	REM & DISP UNS MATL	CU YD	10,909.000				
20400800	FURNISHED EXCAVATION	CU YD	2,477.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20800150	TRENCH BACKFILL	CU YD	3,520.000				
21101615	TOPSOIL F & P 4	SQ YD	60,975.000				
25000210	SEEDING CL 2A	ACRE	8.500				
25000314	SEEDING CL 4B	ACRE	0.500				
25000400	NITROGEN FERT NUTR	POUND	988.000				
25000500	PHOSPHORUS FERT NUTR	POUND	988.000				
25000600	POTASSIUM FERT NUTR	POUND	988.000				
25000750	MOWING	ACRE	9.000				
25100115	MULCH METHOD 2	ACRE	9.000				
25100630	EROSION CONTR BLANKET	SQ YD	88,943.000				
25100900	TURF REINF MAT	SQ YD	2,611.000				
25200110	SODDING SALT TOLERANT	SQ YD	17,603.000				
25200200	SUPPLE WATERING	UNIT	158.000				
28000250	TEMP EROS CONTR SEED	POUND	1,838.000				
28000305	TEMP DITCH CHECKS	FOOT	588.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000400	PERIMETER EROS BAR	FOOT	23,790.000				
28000500	INLET & PIPE PROTECT	EACH	152.000				
28100105	STONE RIPRAP CL A3	SQ YD	136.000				
28100109	STONE RIPRAP CL A5	SQ YD	600.000				
28200200	FILTER FABRIC	SQ YD	600.000				
28500400	ARTICUL BLOCK REV MAT	SQ YD	408.000				
31100910	SUB GRAN MAT A 12	SQ YD	72,665.000				
31100950	SUB GRAN MAT A 21	SQ YD	13,622.000				
35102000	AGG BASE CSE B 8	SQ YD	1,384.000				
35300500	PCC BSE CSE 10	SQ YD	84.000				
40201000	AGGREGATE-TEMP ACCESS	TON	162.000				
40300200	BIT MATLS PR CT	TON	13.100				
40600215	P BIT MATLS PR CT	TON	7.000				
40600300	AGG PR CT	TON	23.000				
40600525	LEV BIND HM N50	TON	112.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600837	P LEV BIND MM N70	TON	153.000				
40600990	TEMPORARY RAMP	SQ YD	279.000				
40603080	HMA BC IL-19.0 N50	TON	1,419.000				
40603235	P HMA BC IL19.0 N70	TON	2,425.000				
40603310	HMA SC "C" N50	TON	1,004.000				
40603565	P HMA SC "E" N70	TON	598.000				
40800050	INCIDENTAL HMA SURF	TON	182.000				
42000306	PCC PVT 8 1/4 JOINTD	SQ YD	2,559.000				
42000411	PCC PVT 9 1/2 JOINTD	SQ YD	59,782.000				
42300300	PCC DRIVEWAY PAVT 7	SQ YD	913.000				
44000100	PAVEMENT REM	SQ YD	52,956.000				
44000155	HMA SURF REM 1 1/2	SQ YD	259.000				
44000158	HMA SURF REM 2 1/4	SQ YD	2,664.000				
44000200	DRIVE PAVEMENT REM	SQ YD	1,370.000				
44000500	COMB CURB GUTTER REM	FOOT	12,001.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER -

64987

State Job # - C-92-162-10
PPS NBR - 2-02430-0100
County Name - WINNEBAGO - -
Code - 201 - -
District - 2 - -
Section Number - 129K-1

Project Number
NHF-0303/053/

Route
FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44003100	MEDIAN REMOVAL	SQ FT	10,151.000				
44004000	PAVED DITCH REMOVAL	FOOT	523.000				
44004250	PAVED SHLD REMOVAL	SQ YD	6,314.000				
48203021	HMA SHOULDERS 6	SQ YD	115.000				
48300410	PCC SHOULDERS 9 1/2	SQ YD	3,594.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50102400	CONC REM	CU YD	67.300				
50104400	CONC HDWL REM	EACH	2.000				
50105220	PIPE CULVERT REMOV	FOOT	3,710.000				
50200100	STRUCTURE EXCAVATION	CU YD	1,988.000				
50800105	REINFORCEMENT BARS	POUND	65,360.000				
50800205	REINF BARS, EPOXY CTD	POUND	440.000				
51500100	NAME PLATES	EACH	2.000				
54002020	EXPAN BOLTS 3/4	EACH	90.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54003000	CONC BOX CUL	CU YD	368.300				
54011106	PCBC 11X6	FOOT	1,060.000				
54213657	PRC FLAR END SEC 12	EACH	13.000				
54213660	PRC FLAR END SEC 15	EACH	5.000				
54213663	PRC FLAR END SEC 18	EACH	3.000				
54213669	PRC FLAR END SEC 24	EACH	3.000				
54213675	PRC FLAR END SEC 30	EACH	1.000				
550A0050	STORM SEW CL A 1 12	FOOT	1,950.000				
550A0070	STORM SEW CL A 1 15	FOOT	914.000				
550A0090	STORM SEW CL A 1 18	FOOT	198.000				
550A0110	STORM SEW CL A 1 21	FOOT	331.000				
550A0120	STORM SEW CL A 1 24	FOOT	565.000				
550A0140	STORM SEW CL A 1 30	FOOT	278.000				
550A0160	STORM SEW CL A 1 36	FOOT	25.000				
550A0340	STORM SEW CL A 2 12	FOOT	599.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0360	STORM SEW CL A 2 15	FOOT	157.000				
550A0380	STORM SEW CL A 2 18	FOOT	125.000				
550A0400	STORM SEW CL A 2 21	FOOT	700.000				
550A0410	STORM SEW CL A 2 24	FOOT	162.000				
550A0430	STORM SEW CL A 2 30	FOOT	118.000				
550A0450	STORM SEW CL A 2 36	FOOT	117.000				
550A0480	STORM SEW CL A 2 48	FOOT	798.000				
56100700	WATER MAIN 8	FOOT	125.000				
56105000	WATER VALVES 8	EACH	1.000				
56400100	FIRE HYDNNTS TO BE MVD	EACH	2.000				
56400500	FIRE HYDNNTS TO BE REM	EACH	2.000				
56400810	FIRE HYDRANT EXTEN	FOOT	20.000				
56400820	FIRE HYD W/AUX V & VB	EACH	2.000				
56500600	DOM WAT SER BOX ADJ	EACH	2.000				
56500700	DOM WAT SER BOX REM	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60218400	MAN TA 4 DIA T1F CL	EACH	4.000				
60219300	MAN TA 4 DIA T11F&G	EACH	3.000				
60221700	MAN TA 5 DIA T8G	EACH	1.000				
60223700	MAN TA 6 DIA T1F OL	EACH	1.000				
60224446	MAN TA 7 DIA T1F CL	EACH	1.000				
60224449	MAN TA 7 DIA T24F&G	EACH	1.000				
60236200	INLETS TA T8G	EACH	3.000				
60236800	INLETS TA T11F&G	EACH	1.000				
60240215	INLETS TB T1F CL	EACH	1.000				
60240310	INLETS TB T11F&G	EACH	8.000				
60255500	MAN ADJUST	EACH	7.000				
60260100	INLETS ADJUST	EACH	6.000				
60265700	VV ADJUST	EACH	2.000				
60266100	VV RECONST	EACH	3.000				
60266600	VALVE BOX ADJ	EACH	14.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500040	REMOV MANHOLES	EACH	7.000				
60500060	REMOV INLETS	EACH	35.000				
60500070	REMOV MAN - MAIN FLOW	EACH	1.000				
60600095	CLASS SI CONC OUTLET	CU YD	15.000				
60603500	COMB CC&G TB6.06	FOOT	844.000				
60603800	COMB CC&G TB6.12	FOOT	3,305.000				
60604400	COMB CC&G TB6.18	FOOT	2,605.000				
60605000	COMB CC&G TB6.24	FOOT	16,913.000				
60608600	COMB CC&G TM6.06	FOOT	456.000				
60610400	COMB CC&G TM6.24	FOOT	622.000				
60618208	HMA MEDIAN	SQ FT	20,887.000				
60618300	CONC MEDIAN SURF 4	SQ FT	465.000				
60619200	CONC MED TSB6.06	SQ FT	378.000				
60624600	CORRUGATED MED	SQ FT	1,629.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	475.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63000025	SPBGR ATTACH TO STR	FOOT	112.500				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	1,218.000				
63500105	DELINEATORS	EACH	8.000				
66700305	PERM SURV MKRS T2	EACH	3.000				
67000400	ENGR FIELD OFFICE A	CAL MO	24.000				
67100100	MOBILIZATION	L SUM	1.000				
*ADD 66900200	NON SPL WASTE DISPOSL	CU YD	10.000				
*ADD 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
*ADD 66900530	SOIL DISPOSAL ANALY	EACH	1.000				
70100320	TRAF CONT-PROT 701422	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	128.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70106800	CHANGEABLE MESSAGE SN	CAL MO	84.000				
70300100	SHORT TERM PAVT MKING	FOOT	2,000.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	6,057.000				
70300220	TEMP PVT MK LINE 4	FOOT	207,627.000				
70300250	TEMP PVT MK LINE 8	FOOT	23,572.000				
70300280	TEMP PVT MK LINE 24	FOOT	3,801.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	45,940.000				
70400100	TEMP CONC BARRIER	FOOT	3,075.000				
70400200	REL TEMP CONC BARRIER	FOOT	8,712.500				
72000100	SIGN PANEL T1	SQ FT	91.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	2,813.200				
78008210	POLYUREA PM T1 LN 4	FOOT	26,060.000				
78008230	POLYUREA PM T1 LN 6	FOOT	3,212.000				
78008240	POLYUREA PM T1 LN 8	FOOT	17,495.000				
78008250	POLYUREA PM T1 LN 12	FOOT	2,551.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008270	POLYUREA PM T1 LN 24	FOOT	1,269.000				
78100100	RAISED REFL PAVT MKR	EACH	793.000				
78200410	GUARDRAIL MKR TYPE A	EACH	26.000				
78201000	TERMINAL MARKER - DA	EACH	2.000				
78300100	PAVT MARKING REMOVAL	SQ FT	3,955.000				
81012500	CON T 1 1/2 PVC	FOOT	96.000				
81012700	CON T 2 1/2 PVC	FOOT	1,517.000				
81013000	CON T 4 PVC	FOOT	406.000				
81018600	CON P 2 1/2 GALVS	FOOT	398.000				
81018900	CON P 4 GALVS	FOOT	2,082.000				
81400100	HANDHOLE	EACH	32.000				
81400300	DBL HANDHOLE	EACH	4.000				
81702110	EC C XLP USE 1C 10	FOOT	7,936.000				
81900200	TR & BKFIL F ELECT WK	FOOT	2,019.000				
* 82102250	LUM SV HOR MT 250W	EACH	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 82102400	LUM SV HOR MT 400W	EACH	4.000				
*ADD 84200600	REM LT U NO SALV	EACH	13.000				
*ADD 84200804	REM POLE FDN	EACH	13.000				
*ADD 84500110	REMOV LIGHTING CONTR	EACH	1.000				
*ADD 84500120	REMOV ELECT SERV INST	EACH	1.000				
*ADD 84500130	REMOV LTG CONTR FDN	EACH	1.000				
85700300	FAC T5 CAB	EACH	4.000				
86000100	MASTER CONTROLLER	EACH	1.000				
*ADD 86200200	UNINTER POWER SUP STD	EACH	4.000				
87100110	FO CAB C 62.5/125 6F	FOOT	1,891.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	4,455.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	21,263.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	2,402.000				
87301295	ELCBL C SIGNAL 20 3C	FOOT	4,455.000				
87301815	ELCBL C SERV 6 3C	FOOT	96.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301900	ELCBL C EGRDC 6 1C	FOOT	4,518.000				
87800100	CONC FDN TY A	FOOT	36.000				
87800200	CONC FDN TY D	FOOT	12.000				
87800400	CONC FDN TY E 30D	FOOT	10.000				
87800415	CONC FDN TY E 36D	FOOT	184.000				
87800420	CONC FDN TY E 42D	FOOT	67.000				
88040070	SH P LED 1F 3S BM	EACH	35.000				
88040090	SH P LED 1F 3S MAM	EACH	51.000				
88040120	SH P LED 1F 4S MAM	EACH	2.000				
88040150	SH P LED 1F 5S BM	EACH	2.000				
88040160	SH P LED 1F 5S MAM	EACH	4.000				
88200100	TS BACKPLATE	EACH	57.000				
89000100	TEMP TR SIG INSTALL	EACH	4.000				
89000105	TEMP TR SIG INSTAL SP	EACH	1.000				
89501300	RELOC EX MAA & POLE	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 64987

State Job # - C-92-162-10
 PPS NBR - 2-02430-0100
 County Name - WINNEBAGO - -
 Code - 201 - -
 District - 2 - -
 Section Number - 129K-1

Project Number
 NHF-0303/053/

Route
 FAP 303

* REVISE : JUNE 07, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD 89501400	REL EM VEH PR SYS D U	EACH	3.000				
89502375	REMOV EX TS EQUIP	EACH	4.000				
89502380	REMOV EX HANDHOLE	EACH	23.000				
89502382	REMOV EX DBL HANDHOLE	EACH	3.000				
89502385	REMOV EX CONC FDN	EACH	24.000				

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE).....	118
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....	122
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	123
TEMPORARY EROSION CONTROL (BDE)	124
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE)	127
UTILITY COORDINATION AND CONFLICTS (BDE).....	127
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)	133
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	136
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	140
IEPA PERMIT	144
IDNR PERMIT	147
404 PERMIT.....	150
NATIONWIDE PERMITS AND CONDITIONS.....	152
STORM WATER POLLUTION PREVENTION PLAN.....	165
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT.....	174
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	174

REVISED 06/08/2011

RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT

This work shall be done according to Section 895 of the "Standard Specifications for Road and Bridge Construction". This work shall consist of removing the emergency vehicle priority systems from existing traffic signal equipment and relocating them to new traffic signal equipment at the intersections of Illinois Route 173 and Illinois Route 251, Orlando Street, and North Alpine Road. The Contractor shall provide any additional material and labor necessary to reconnect the emergency vehicle priority systems to the new traffic signal systems.

Basis of Payment:

This work shall be paid for at the contract unit price per each for RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT. Price shall include all material, equipment and labor necessary to complete this work as specified to the satisfaction of the Engineer.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.

A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.

1. Station 2132+40 to Station 2133+50 0 to 70 feet RT (Tredroc Tire Service, Site 1497V-7, 875 Ralston Road) – non-special waste. Contaminants of concern sampling parameters: PNAs.

Added 06/08/2011