

SUMMARY OF QUANTITIES

				CONSTRUCTION CODE											
				80% FED 20% STATE	80% FED 20% STATE SN. 101-2051	80% FED 20% STATE SN. 101-2052	80% FED 20% STATE SN. 101-2004	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% COUNTY 10% VILLAGE	75% STATE 25% VILLAGE	100% VILLAGE	100% FPD	100% RRWRD	100% NPPWD
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	RET WALL 0040 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	ROADWAY 0021 URBAN	TRAFF SIGNALS 0021 URBAN	UTILITY 0043 URBAN	UTILITY 0043 URBAN
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,605	2,605											
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	16,913	16,913											
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	456	456											
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	622	622											
60618208	HOT-MIX ASPHALT MEDIAN	SQ FT	20,887	20,887											
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	465	465											
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	378	378											
60624600	CORRUGATED MEDIAN	SQ FT	1,629	1,629											
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	475.0	475.0											
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	112.5	112.5											
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2											
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2											
63200310	GUARDRAIL REMOVAL	FOOT	1,218	1,218											
63500105	DELINEATORS	EACH	8	8											
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3											
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10	10											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24											
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1											
67100100	MOBILIZATION	L SUM	1	1											
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1											
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1											
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1											
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	128	128											
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	84	84											
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,000	2,000											
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	6,057	6,057											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	207,627	207,627											
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	23,572	23,572											
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,801	3,801											
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	45,940	45,940											

* SPECIALTY ITEMS ** NON-PARTICIPATING ITEMS

FILE NAME = 0264987-ahf-S00-001.dgn	USER NAME = 3282879971	DESIGNED - LOM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.P RTE. 303	SECTION 129K-1	COUNTY WINNEBAGO	TOTAL SHEETS 401	SHEET NO. 9
	PLOT SCALE = 100.0000' / IN.	DRAWN - MD	REVISED -				CONTRACT NO. 64987				
	CHECKED - PDK	REVISED -	FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT								
	PLOT DATE = 3/16/2011	DATE - 03-16-2011	REVISED -								

Rev. 6-7-11