

SUMMARY OF QUANTITIES

				CONSTRUCTION CODE											
				80% FED 20% STATE	80% FED 20% STATE SN. 101-2051	80% FED 20% STATE SN. 101-2052	80% FED 20% STATE SN. 101-2004	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% COUNTY 10% VILLAGE	75% STATE 25% VILLAGE	100% VILLAGE	100% FPD	100% RRWRD	100% NPPWD
				ROADWAY 0003 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	RET WALL 0040 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	ROADWAY 0021 URBAN	TRAFF SIGNALS 0021 URBAN	UTILITY 0043 URBAN	UTILITY 0043 URBAN
CODE NO.	ITEM	UNIT	TOTAL QUANTITY												
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3,075.0	3,075.0											
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	8,712.5	8,712.5											
72000100	SIGN PANEL - TYPE 1	SQ FT	91						81	10					
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	2,813.2	2,813.2											
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	26,060	26,060											
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	3,212	3,212											
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	17,495	17,495											
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	2,551	2,551											
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1,269	1,269											
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	793	793											
78200410	GUARDRAIL MARKERS, TYPE A	EACH	26	26											
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2											
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,955	3,955											
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	96						79	17					
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	1,517						1474	43					
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	406						125	281					
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	398						398						
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,082						1948	134					
81400100	HANDHOLE	EACH	32						29	3					
81400300	DOUBLE HANDHOLE	EACH	4						3	1					
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	7,936						6,066	1,870					
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,019						1678	341					
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4						4	4					
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12												
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	4						3	1					
86000100	MASTER CONTROLLER	EACH	1						1						
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	1,891						1,891						
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4,455						3,497	958					
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	21,263						19,127	2,136					
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,402						1,414	988					

• SPECIALTY ITEMS

• NON-PARTICIPATING ITEMS

FILE NAME = 0264987-sht-S00-001.dgn

USER NAME = 3282090971

PLOT SCALE = 100.0000 ' / IN.

PLOT DATE = 3/16/2011

DESIGNED - LOM

DRAWN - MD

CHECKED - PDK

DATE - 03-16-2011

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 303

SECTION 129K-1

COUNTY WINNEBAGO

TOTAL SHEETS 401

SHEET NO. 10

CONTRACT NO. 64987

FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT

Rev. 6-6-11