

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				80% FED 20% STATE	80% FED 20% STATE SN. 101-2051	80% FED 20% STATE SN. 101-2052	80% FED 20% STATE SN. 101-2004	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% COUNTY 10% VILLAGE	75% STATE 25% VILLAGE	100% VILLAGE	100% FPD	100% RRWRD	100% NPPWD		
				ROADWAY 0003 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	RET WALL 0040 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	ROADWAY 0021 URBAN	TRAFF SIGNALS 0021 URBAN	UTILITY 0043 URBAN	UTILITY 0043 URBAN		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1,384	1,384													
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	84	84													
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	162	162													
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.1	13.1													
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	7.0	7.0													
40600300	AGGREGATE (PRIME COAT)	TON	23	23													
40600525	LEVELING BINDER (HAND METHOD), N50	TON	112	112													
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	153	153													
40600990	TEMPORARY RAMP	SQ YD	279	279													
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,419	1,419													
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,425	2,425													
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,004	1,004													
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	598	598													
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	182	182													
42000306	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/4" (JOINTED)	SQ YD	2,559	2,559													
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	59,782	59,782													
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	913	913													
44000100	PAVEMENT REMOVAL	SQ YD	52,956	52,956													
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	259	259													
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,664	2,664													
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,370	1,370													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,001	12,001													
44003100	MEDIAN REMOVAL	SQ FT	10,151	10,151													
44004000	PAVED DITCH REMOVAL	FOOT	523	523													
44004250	PAVED SHOULDER REMOVAL	SQ YD	6,314	6,314													
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	115	115													
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	3,594	3,594													
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1											
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1										

* SPECIALTY ITEMS ** NON-PARTICIPATING ITEMS		FILE NAME = 0264987-shl 500 001.dgn		USER NAME = 320289871		DESIGNED - LOM		REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE. 303		SECTION 129K-1		COUNTY WINNEBAGO		TOTAL SHEETS 401		SHEET NO. 6	
PLOT SCALE = 1/8" = 1' / IN.		PLOT DATE = 3/16/2011		DRAWN - MD		CHECKED - PDK		DATE - 03-16-2011		SCALE:				SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT									
																		CONTRACT NO. 64987									