

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				80% FED 20% STATE	80% FED 20% STATE SN. 101-2051	80% FED 20% STATE SN. 101-2052	80% FED 20% STATE SN. 101-2004	80% FED 20% STATE	80% FED 20% STATE	80% FED 10% COUNTY 10% VILLAGE	75% STATE 25% VILLAGE	100% VILLAGE	100% FPD	100% RRWRD	100% NPPWD			
				ROADWAY 0003 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	BOX CULVERT 0040 URBAN	RET WALL 0040 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	TRAFF SIGNALS 0021 URBAN	ROADWAY 0021 URBAN	TRAFF SIGNALS 0021 URBAN	UTILITY 0043 URBAN	UTILITY 0043 URBAN		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,605	2,605														
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	16,913	16,913														
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	456	456														
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	622	622														
60618208	HOT-MIX ASPHALT MEDIAN	SQ FT	20,887	20,887														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	465	465														
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	378	378														
60624600	CORRUGATED MEDIAN	SQ FT	1,629	1,629														
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	475.0	475.0														
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	112.5	112.5														
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2														
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2														
63200310	GUARDRAIL REMOVAL	FOOT	1,218	1,218														
63500105	DELINEATORS	EACH	8	8														
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24														
67100100	MOBILIZATION	L SUM	1	1														
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	128	128														
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	84	84														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,000	2,000														
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	6,057	6,057														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	207,627	207,627														
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	23,572	23,572														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,801	3,801														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	45,940	45,940														