

SCHEDULE OF QUANTITIES

LOCATION			PRE- STAGE 1		PRE- STAGE 2		PRE- STAGE 3	WINTER STAGE
STATION TO STATION	OFFSET	70400100	70400200	70400100	70400200	70400200	70400200	
		TEMP CONC BARRIER	REL TEMP CONC BARRIER	TEMP CONC BARRIER	REL TEMP CONC BARRIER	REL TEMP CONC BARRIER	REL TEMP CONC BARRIER	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
RALSTON ROAD/IL 173								
1005+45.15	1010+41.82	RT	500.0					
1007+67.18	1011+29.69	LT	350.0					
1006+65.33	1011+80.97	LT			87.5	425.0		
1006+68.62	1010+92.99	RT				425.0		
1007+29.45	110+85.07	RT					362.5	
ROUTE 251								
858+80.00	861+58.73	LT						275.0
863+12.50	865+91.24	RT						275.0
880+20.00	882+23.69	LT						200.0
SUB-TOTAL			850.0	0.0	87.5	850.0	362.5	750.0

LOCATION			STAGE 1 A		STAGE 1 B	STAGE 1 C	STAGE 2 A	STAGE 2 B	STAGE 2 C
STATION TO STATION	OFFSET	70400100	70400200	70400200	70400200	70400200	70400200	70400200	70400200
		TEMP CONC BARRIER	REL TEMP CONC	REL TEMP CONC	REL TEMP CONC BARRIER	REL TEMP CONC BARRIER	REL TEMP CONC BARRIER	REL TEMP CONC	
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL 173									
1018+14.58	1019+11.47	LT		150.0					
1019+56.51	1024+36.79	LT		662.5					
1019+51.80	1020+45.59	RT		112.5					
1018+00.14	119+77.52	RT				175.0			
1018+32.81	1019+61.41	RT					225.0		
1020+06.30	1024+61.99	RT					575.0		
IL ROUTE 251									
858+58.44	869+47.08	LT/RT	1075.0						
869+47.08	869+59.78			12.5					
858+58.44	870+10.46	LT/RT						1137.5	
863+16.10	865+83.95	RT			262.5				
858+73.80	861+52.31	RT			275.0				
860+26.54	869+75.29	RT			950.0				
866+19.27	867+82.40	LT							162.5
869+75.29	870+13.30	RT					37.5		
871+30.30	882+03.28	LT/RT	1062.5						
871+44.56	881+70.81	RT			1012.5				
871+93.65	882+03.28	LT/RT						1000.0	
SUB-TOTAL			2137.5	937.5	2500.0	175.0	837.5	2137.5	162.5

70400100 TEMPORARY CONCRETE BARRIER, TOTAL=	3075.0	FOOT
70400200 RELOCATE TEMPORARY CONCRETE BARRIER, TOTAL=	8712.5	FOOT