

MEDIAN, CURB, & SIDEWALK SCHEDULE														
DESCRIPTION	LOCATION	SUGGESTED METHOD	COMB CURB & GUTTER REM	SIDEWALK REM	CCC&G TYPE B-6.12	CCC&G TYPE B-6.24	PCC SIDEWALK 4"	DETECTABLE WARNINGS	SOD SALT TOLERANT	NIT FERT NUT	PHOS FERT NUT	POT FERT NUT	HH TO BE ADJ	MH ADJ TO BE ADJ
			FOOT	SQ FT	FOOT	FOOT	SQ FT	SQ FT	SQ YD	LB	LB	LB	EACH	EACH
NORTHBOUND LASALLE														
Main St.														
	NE	Method 1 C	23	132	23		132	24					1	
	SE	Method 1 C	27	132	27		132	32						
	SW	Method 1 C	24	154	24		154	32					1	
	NW	Method 1 C	30	154	30		154	32						
Bridge St.														
	NE	Method 1 C	26	178	26		178	32					1	
	SE	Method 1 C	27	178	27		178	32					2	
	SW	Method 1 C	28	225		28	225	32						
	NW	Method 1 C	26	132	26		132	16					1	
Wilson St.														
	NE	Method 2 E	36	165		36	165	16	11	0.3	0.3	0.3		
	SE	Method 3 F	27	75		27	75	16	8	0.2	0.2	0.2		
	SW	Method 1 A	14	90		14	90	8	8	0.2	0.2	0.2		
	NW	Method 2 E	27	155		27	155	16	11	0.3	0.3	0.3		
E. Livingston St.														
	NE	Method 2 E	27	180		27	180	8	12	0.3	0.3	0.3		
	SE	Method 1 A	28	175		28	175	16	12	0.3	0.3	0.3		
	SW	Method 1 B	26	150		26	150	16	11	0.3	0.3	0.3		
	NW	Method 1 B	27	195		27	195	8	11	0.3	0.3	0.3		
Lundy St.														
	NE	Method 1 C	27	176	27		176	32						
	SE	Method 1 C	17	165		17	165	24	10	0.2	0.2	0.2		
	SW	Method 1 C	27	163		27	163	24	10	0.2	0.2	0.2		
	NW	Method 1 C	27	195	27		195	32	1	0.1	0.1	0.1		
Spring St.														
	NE	Method 1 C	15	125	15		125	32	4	0.1	0.1	0.1		
	SE	Method 1 C	25	140	25		140	32	2	0.1	0.1	0.1		
	SW	Method 1 B	16	215		16	215	16	4	0.1	0.1	0.1		
	NW	Method 1 C	29	110	29		110	24	3	0.1	0.1	0.1		
STA 566+89														
STA 566+89														
	E	Method 1 A	20	100	15		100	8	6	0.2	0.2	0.2		
	W	Method 1 A	20	100	15		100	8	6	0.2	0.2	0.2		
Brumbach St														
	NE	Method 4 G	12	56	12		56	8		0.0	0.0	0.0		
	SE	Method 1 A	6	90	6		90	8	6	0.2	0.2	0.2		
	SW	Method 1 A	8	80		8	80	8	6	0.2	0.2	0.2		
	NW	Method 6 J	8	110		8	110	8	6	0.2	0.2	0.2		
Cottage St														
E. Lee St.														
	NE	Method 1 A	6	48		6	48	8	6	0.1	0.1	0.1		
	SW	Method 1 A	6	48		2	48	8	6	0.2	0.2	0.2		
	NW	Method 1 A	6	60		6	60	8	6	0.2	0.2	0.2		
10th St														
	NE	Method 1 A	6	40	6		40	8	6	0.2	0.2	0.2		
	SE	Method 1 A	6	50	6		50	8	6	0.2	0.2	0.2		
Sangamon St														
	NW	Method 3 F	10	50		5	50	8	6	0.2	0.2	0.2		
	SW	Method 3 F	10	50		5	50	8	6	0.2	0.0	0.0		
LASALLE TOTAL			1305	8532	517	703	8477	1112	435	11.1	11.1	11.1	9	1
Northbound Livingston														
12th St														
	NW	Method 1 B	12	80		8	80	16	8	0.2	0.2	0.2		
	NE	Method 1 B	12	80		8	80	16	8	0.2	0.2	0.2		
LIVINGSTON TOTAL			24	160	0	16	160	32	16	0.4	0.4	0.4	0	0
NORTHBOUND TOTAL			1329	8692	517	719	8637	1144	451	12.0	12.0	12.0	9	1