

SUMMARY OF QUANTITIES				URBAN 80% FED. / 20% STATE CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005	
20101700	SUPPLEMENTAL WATERING	UNIT	2	2	
25200110	SODDING, SALT TOLERANT	SQ YD	223	223	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2429	2429	
40600300	AGGREGATE (PRIME COAT)	TON	37	37	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	9	9	
40600990	TEMPORARY RAMP	SQ YD	231	231	
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1503	1503	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	100	100	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	2174	2174	
42400800	DETECTABLE WARNINGS	SQ FT	656	656	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	18684	18684	
44000600	SIDEWALK REMOVAL	SQ FT	1628	1628	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2934	2934	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	158	158	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1890	1890	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2750	2750	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	259	259	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	395	395	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	112	112	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	242	242	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	158	158	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2118	2118	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2750	2750	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	534	534	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	395	395	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	112	112	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	52	
88600100	DETECTOR LOOP, TYPE I	FOOT	732	732	
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	751	751	
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	502	502	
X6061700	COMBINATION CONCRETE CURB AND GUTTER TYPE B (SPECIAL)	FOOT	502	502	

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboygc	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\braboygc\d0122683\036	945-shr-detail1.dgn	DRAWN -	REVISED -					615	(116)RS-6	BUREAU	14	3
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66945		
	PLOT DATE = Mar 17, 2011 - 10:53:03 AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							