

D:\10052607\20073026-08\acad\atrr\00\0366955-ent-500-01.dgn
3/24/2011 12:04:53 PM

SP	SI	SUMMARY OF QUANTITIES				URBAN		
					TOTAL QUANTITY	90% FED/ 10% STATE	90% FED/ 5% STATE/ 5% COUNTY	100% COUNTY
		CODE NO.	ITEM	UNIT		ROADWAY	TRAFFIC SIGNALS	LIGHTING
						0005	0021	0021
	*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	109	109		
		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	57	57		
		20101000	TEMPORARY FENCE	FOOT	231	231		
		20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	6	6		
		20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	26	26		
		20200100	EARTH EXCAVATION	CU YD	6,083	6,083		
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,000	1,000		
		20400800	FURNISHED EXCAVATION	CU YD	118	118		
		20800150	TRENCH BACKFILL	CU YD	14	14		
		25000210	SEEDING, CLASS 2A	ACRE	1.83	1.83		
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	164	164		
		25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	164	164		
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	164	164		
		25100630	EROSION CONTROL BLANKET	SQ YD	7,767	7,767		
		25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1,077	1,077		
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	183	183		
		28000305	TEMPORARY DITCH CHECKS	FOOT	240	240		
		28000400	PERIMETER EROSION BARRIER	FOOT	4,871	4,871		
		28100109	STONE RIPRAP, CLASS A5	SQ YD	44	44		
		31100500	SUBBASE GRANULAR MATERIAL, TYPE A, 6"	SQ YD	4,562	4,562		
		31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	142	142		
		35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	445	445		
		35600722	HOT-MIX ASPHALT BASE COURSE WIDENING, 11 1/2"	SQ YD	1,083	1,083		
		40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50	50		
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,667	2,667		
		40600300	AGGREGATE (PRIME COAT)	TON	23.9	23.9		
		40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2.9	2.9		
		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	100.3	100.3		
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	755	755		
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,011.5	1,011.5		
		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,405.0	1,405.0		
		44004000	PAVED DITCH REMOVAL	FOOT	95	95		
		44004250	PAVED SHOULDER REMOVAL	SQ YD	1,581	1,581		
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,170	2,170		
		48101600	AGGREGATE SHOULDERS, TYPE B, 8"	SQ YD	449	449		
		50105220	PIPE CULVERT REMOVAL	FOOT	167	167		
		542A0223	PIPE CULVERTS, CLASS A, TYPE 1, 18"	FOOT	16	16		
		542D5470	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND SIZE 15"	FOOT	187	187		
		54213447	END SECTIONS, 12"	EACH	1	1		
		54213453	END SECTIONS, 18"	EACH	1	1		
		54214290	END SECTIONS, EQUIVALENT ROUND SIZE 15"	EACH	10	10		
		60100945	PIPE DRAINS, 12"	FOOT	5	5		
		60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1		
		60615910	PAVED DITCH, TYPE A-22	FOOT	80	80		

*	DENOTES SPECIAL PROVISION
**	DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - JWB	REVISED -
		DRAWN - JWB	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - RS	REVISED -
	PLOT DATE = 3/31/2011	DATE - 03/31/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(I-1)N TS	KENDALL	92	3
CONTRACT NO. 66955				
ILLINOIS FED. AID PROJECT				