

SP	SI	SUMMARY OF QUANTITIES				URBAN		
					TOTAL QUANTITY	90% FED/ 10% STATE	90% FED/ 5% STATE/ 5% COUNTY	100% COUNTY
		CODE NO.	ITEM	UNIT		ROADWAY	TRAFFIC SIGNALS	LIGHTING
	*					0005	0021	0021
	**	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,435		1,435	
	**	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	931		931	
	**	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,001		1,001	
	**	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,204		3,204	
	**	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	108		108	
	**	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,656		1,656	
	**	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4			4
	**	87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1		1	
	**	87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1		1	
	**	87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1		1	
	**	87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1		1	
	**	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16	
	**	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
	**	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	58		58	
	*	88000105	FLASHING BEACON INSTALLATION	EACH	2		2	
	**	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
	**	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION,MAST-ARM MOUNTED	EACH	4		4	
	**	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION,BRACKET MOUNTED	EACH	5		5	
	**	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION,MAST-ARM MOUNTED	EACH	5		5	
	**	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	15		15	
	**	88500100	INDUCTIVE LOOP DETECTOR	EACH	17		17	
	**	88600100	DETECTOR LOOP, TYPE I	FOOT	1,763		1,763	
	*	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	240	240		
	*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
	*	Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	3,000	3,000		
	*	Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	5	5		
	*	Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		

*	DENOTES SPECIAL PROVISION
**	DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - JWB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS SUMMARY OF QUANTITIES	SCALE: N.T.S.	SHEET NO. OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JWB	REVISED -					311	(1)-1IN TS	KENDALL	92	5
	PLOT SCALE = 50.0000' / IN.	CHECKED - RS	REVISED -					CONTRACT NO. 66955				
	PLOT DATE = 3/31/2011	DATE - 03/31/2011	REVISED -					ILLINOIS FED. AID PROJECT				

net:\pbe2007\20075028-08\cad\stf\rev\don\00\0366955-ent-500-03.dgn
3/3/2011 12:04:53 PM