

\\jobs2007\20071028-08\cod\site\adgn\00_0366955-snt-schedule-0.dgn
3/31/2011 12:05:36 PM

TREE REMOVAL AND MAINTENANCE SCHEDULE

						20100110	20100210	20101000	20101300	20101350
STATION	OFFSET	SIZE-DIA. INCHES (SURVEY)	SIZE-DIA. INCHES (START OF CNSTRCTN)	TYPE	ACTION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TEMPORARY FENCE (FOOT)	TREE PRUNING (1 TO 10 INCH DIAMETER) (EACH)	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH)
54+44.8	LT	35.0	13.0		PROTECT	0	0	0	0	1
54+65.9	LT	34.9	13.0	STUMP	REMOVE	1	0	0	0	0
54+73.9	LT	35.7	11.0		PROTECT	0	0	0	0	1
54+75.4	RT	31.2	7.0		REMOVE	1	0	0	0	0
54+87.7	LT	33.7	7.0		REMOVE	1	0	0	0	0
54+93.6	LT	34.6	13.0		REMOVE	1	0	0	0	0
55+10.4	LT	34.9	11.0	STUMP	REMOVE	1	0	0	0	0
55+15.3	LT	34.0	7.0	STUMP	REMOVE	1	0	0	0	0
55+34.0	LT	35.4	8.0		REMOVE	1	0	0	0	0
55+34.6	LT	55.0	23.0		PROTECT	0	0	0	0	1
55+35.9	LT	56.6	17.0		PROTECT	0	0	0	0	1
55+36.0	LT	35.3	6.0		REMOVE	1	0	0	0	0
55+36.6	LT	57.5	6.0		PROTECT	0	0	0	1	0
55+36.9	LT	36.0	6.0		REMOVE	1	0	0	0	0
55+43.0	LT	37.3	6.0		REMOVE	1	0	0	0	0
55+43.3	LT	39.7	6.0		REMOVE	1	0	0	0	0
55+60.0	LT	48.6	11.0		REMOVE	1	0	0	0	0
55+62.9	RT	35.7	6.0		PROTECT	0	0	0	1	0
55+64.4	LT	37.8	10.0		REMOVE	1	0	0	0	0
55+68.9	LT	47.9	9.0		REMOVE	1	0	0	0	0
55+69.0	LT	46.1	8.0		REMOVE	1	0	0	0	0
55+72.8	LT	37.0	7.0		REMOVE	1	0	0	0	0
55+83.1	LT	38.6	6.0	STUMP	REMOVE	1	0	0	0	0
55+86.0	LT	43.6	8.0		REMOVE	1	0	0	0	0
55+92.9	LT	42.0	8.0		REMOVE	1	0	0	0	0
55+95.3	LT	43.2	6.0		REMOVE	1	0	0	0	0
55+96.4	LT	52.0	8.0		REMOVE	1	0	0	0	0
56+15.9	LT	35.5	12		REMOVE	1	0	0	0	0
56+18.4	LT	35.3	8		REMOVE	1	0	0	0	0
56+27.5	LT	33.9	12		REMOVE	1	0	0	0	0
56+30.5	LT	35.0	12		REMOVE	1	0	0	0	0
56+39.2	LT	34.9	8		REMOVE	1	0	0	0	0
56+39.4	LT	36.4	12		REMOVE	1	0	0	0	0
56+44.8	LT	36.6	12		REMOVE	1	0	0	0	0
56+45.1	LT	33.0	12		REMOVE	1	0	0	0	0
56+45.2	LT	31.7	12		REMOVE	1	0	0	0	0
56+51.5	LT	35.8	12		REMOVE	1	0	0	0	0
56+55.5	LT	35.0	12		REMOVE	1	0	0	0	0
56+57.0	LT	33.3	8		REMOVE	1	0	0	0	0
56+59.6	LT	34.8	18		REMOVE	0	1	0	0	0
56+60.0	LT	32.6	8		REMOVE	1	0	0	0	0
56+68.5	LT	32.3	10		REMOVE	1	0	0	0	0
56+73.2	LT	33.1	8		REMOVE	1	0	0	0	0
56+78.3	LT	32.9	6		REMOVE	1	0	0	0	0
56+82.4	LT	34.5	10		REMOVE	1	0	0	0	0
56+82.7	LT	37.1	14		REMOVE	0	1	0	0	0
56+85.4	LT	33.1	24		REMOVE	0	1	0	0	0
56+91.3	LT	33.2	14		REMOVE	0	1	0	0	0
56+91.6	LT	32.0	10		REMOVE	1	0	0	0	0
57+00.0	LT	34.4	18		REMOVE	0	1	0	0	0
57+02.5	LT	33.5	14		REMOVE	0	1	0	0	0
57+06.9	LT	32.7	12		REMOVE	1	0	0	0	0
57+07.0	LT	34.0	10		REMOVE	1	0	0	0	0
57+18.2	LT	32.9	10	STUMP	REMOVE	1	0	0	0	0
57+20.3	LT	34.5	14	STUMP	REMOVE	0	1	0	0	0
57+29.1	LT	32.6	16		REMOVE	0	1	0	0	0
57+49.8	LT	33.1	8		REMOVE	1	0	0	0	0
57+61.4	LT	30..2	18		REMOVE	0	1	0	0	0
57+62.6	LT	36.0	30	STUMP	REMOVE	0	1	0	0	0
57+67.5	LT	37.8		BUSH	REMOVE	1	0	0	0	0
57+77.4	LT	38.7		BUSH	REMOVE	1	0	0	0	0
57+81.2	LT	37.0	12		REMOVE	1	0	0	0	0
58+17.1	LT	40.0		BUSH	REMOVE	1	0	0	0	0
59+32.7	LT	43.8	24		REMOVE	0	1	0	0	0

TREE REMOVAL AND MAINTENANCE SCHEDULE

						20100110	20100210	20101000	20101300	20101350
STATION	OFFSET	SIZE-DIA. INCHES (SURVEY)	SIZE-DIA. INCHES (START OF CNSTRCTN)	TYPE	ACTION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TEMPORARY FENCE (FOOT)	TREE PRUNING (1 TO 10 INCH DIAMETER) (EACH)	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH)
59+69.0	LT	42.5			REMOVE	1	0	0	0	0
59+75.8	LT	33.1	18		REMOVE	0	1	0	0	0
59+78.1	LT	33.8	18		REMOVE	0	1	0	0	0
60+13.3	RT	49.2	10		PROTECT	0	0	0	0	1
60+25.8	RT	53.9	10		REMOVE	1	0	0	0	0
60+26.1	RT	64.7	8		PROTECT	0	0	0	1	0
664+15.3	LT	48.4			PROTECT	0	0	12	0	1
664+16.4	LT	49.4			PROTECT	0	0	12	0	1
664+32.3	LT	49.4			PROTECT	0	0	12	0	1
664+33.4	LT	45.7			PROTECT	0	0	12	0	1
664+33.5	LT	47.7			PROTECT	0	0	12	0	1
664+35.4	LT	48.7			PROTECT	0	0	12	0	1
664+37.4	LT	46.4			PROTECT	0	0	12	0	1
664+43.6	LT	46.2			PROTECT	0	0	12	0	1
664+53.8	LT	47.4			PROTECT	0	0	12	0	1
664+60.1	LT	47.2			PROTECT	0	0	12	1	0
664+73.1	LT	47.8			PROTECT	0	0	12	0	1
665+44.4	LT	40.0			REMOVE	1	0	0	0	0
665+62.2	LT	40.4			REMOVE	1	0	0	0	0
665+67.4	LT	43.2			REMOVE	1	0	0	0	0
665+67.6	LT	45.8			REMOVE	1	0	0	0	0
665+69.3	LT	45.4			REMOVE	1	0	0	0	0
665+69.6	LT	43.2			REMOVE	1	0	0	0	0
665+70.7	LT	45.2			REMOVE	1	0	0	0	0
665+73.3	LT	36.8			REMOVE	1	0	0	0	0
665+79.6	LT	37.3			REMOVE	1	0	0	0	0
665+92.0	LT	40.7			REMOVE	1	0	0	0	0
665+96.5	LT	43.7			REMOVE	1	0	0	0	0
666+12.1	LT	47.6			REMOVE	1	0	0	0	0
666+18.9	LT	48.5			PROTECT	0	0	12	1	0
666+23.7	RT	47.7			REMOVE	1	0	0	0	0
666+27.7	LT	49.6			PROTECT	0	0	12	1	0
666+30.8	LT	49.8			PROTECT	0	0	12	0	1
666+49.7	RT	48.8			REMOVE	0	1	0	0	0
666+50.8	RT	47.6			REMOVE	1	0	0	0	0
666+51.4	LT	49.2			PROTECT	0	0	12	0	1
666+72.0	LT	41.8			REMOVE	1	0	0	0	0
666+73.6	LT	42.2			REMOVE	1	0	0	0	0
666+73.9	RT	47.5			REMOVE	1	0	0	0	0
666+98.1	RT	49.1			REMOVE	0	1	0	0	0
666+98.2	RT	50.0			REMOVE	1	0	0	0	0
667+41.7	LT	44.7			REMOVE	1	0	0	0	0
667+63.7	LT	42.1			REMOVE	1	0	0	0	0
667+63.9	LT	40.9			REMOVE	1	0	0	0	0
667+74.1	LT	47.1			REMOVE	0	1	0	0	0
667+75.4	LT	46.8			REMOVE	1	0	0	0	0
667+76.2	LT	46.3			REMOVE	1	0	0	0	0
667+77.4	RT	46.9			REMOVE	0	1	0	0	0
667+79.3	RT	46.3			REMOVE	0	1	0	0	0
668+20.1	RT	45.3			REMOVE	1	0	0	0	0
668+26.0	LT	39.8			REMOVE	1	0	0	0	0
668+28.0	LT	40.0			REMOVE	1	0	0	0	0
668+38.8	LT	41.0			REMOVE	1	0	0	0	0
668+42.5	LT	40.7			REMOVE	1	0	0	0	0
668+44.0	RT	47.3			REMOVE	1	0	0	0	0
668+44.9	RT	47.6			REMOVE	1	0	0	0	0
669+34.9	RT	50.0			REMOVE	1	0	0	0	0
669+60.8	RT	47.9			REMOVE	1	0	0	0	0
669+61.7	RT	48.2			REMOVE	1	0	0	0	0
670+37.3	LT	48.2		STUMP	REMOVE	0	1	0	0	0
673+15.5	LT	53.2			REMOVE	0	1	0	0	0
673+27.0	LT	55.0			REMOVE	0	1	0	0	0
673+32.3	LT	49.5		STUMP	REMOVE	0	1	0	0	0
673+36.7	LT	49.3			REMOVE	1	0	0	0	0

FILE NAME =	USER NAME = .USER_	DESIGNED - JWB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000 ' / IN.	DRAWN - JWB	REVISED -					311	(1-IN) TS	KENDALL	92	16
	PLOT DATE = 3/31/2011	CHECKED - RS	REVISED -					CONTRACT NO. 66955				
	DATE - 03/31/2011	REVISED -										
				SCALE: N.T.S.	SHEET NO.	OF	SHEETS	ILLINOIS FED. AID PROJECT				