

m:\jobs\2007\2028-08\cadd\site\cgm\00_0366955-sht-schedule-02.dgn
3/31/2011 12:05:40 PM

TREE REMOVAL AND MAINTENANCE SCHEDULE

						20100110	20100210	20101000	20101300	20101350
STATION	OFFSET	SIZE-DIA. INCHES (SURVEY)	SIZE-DIA. INCHES (START OF CNSTRCTN)	TYPE	ACTION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TEMPORARY FENCE (FOOT)	TREE PRUNING (1 TO 10 INCH DIAMETER) (EACH)	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH)
673+38.7	LT	48.4	10		REMOVE	1	0	0	0	0
673+39.0	LT	53.7	14	STUMP	REMOVE	0	1	0	0	0
673+43.3	LT	53.0	8	STUMP	REMOVE	1	0	0	0	0
673+45.0	LT	50.3	10		REMOVE	1	0	0	0	0
673+45.1	LT	47.7	10		REMOVE	1	0	0	0	0
673+46.4	LT	48.6	10		REMOVE	1	0	0	0	0
673+53.7	LT	49.5	12		REMOVE	1	0	0	0	0
673+54.5	LT	52.0	12		REMOVE	1	0	0	0	0
673+55.7	LT	48.7	12		REMOVE	1	0	0	0	0
673+56.9	LT	51.4	6		REMOVE	1	0	0	0	0
673+60.3	LT	47.4	12		REMOVE	1	0	0	0	0
673+62.9	LT	47.3	12		REMOVE	1	0	0	0	0
673+67.6	LT	51.4	30		REMOVE	0	1	0	0	0
674+90.6	LT	53.1	14		REMOVE	0	1	0	0	0
674+91.5	LT	50.2	18		REMOVE	0	1	0	0	0
674+93.7	LT	52.8	18		REMOVE	0	1	0	0	0
674+99.0	LT	49.7	24		REMOVE	0	1	0	0	0
675+08.4	LT	49.8	12		REMOVE	1	0	0	0	0
675+10.2	LT	49.3	12		REMOVE	1	0	0	0	0
675+26.2	LT	48.5	12		REMOVE	1	0	0	0	0
675+27.0	LT	51.4	14		REMOVE	0	1	0	0	0
675+29.4	LT	49.6	14		REMOVE	0	1	0	0	0
675+34.3	LT	52.8	26		REMOVE	0	1	0	0	0
675+44.4	LT	49.3	18		REMOVE	0	1	0	0	0
675+44.7	LT	51.6	12		REMOVE	1	0	0	0	0
675+44.9	LT	52.9	14		REMOVE	0	1	0	0	0
675+45.9	LT	51.5	14		REMOVE	0	1	0	0	0
675+70.1	LT	52.8	10		REMOVE	1	0	0	0	0
675+70.3	LT	50.7	10		REMOVE	1	0	0	0	0
675+74.4	LT	49.0	12		REMOVE	1	0	0	0	0
675+75.5	LT	50.6	10		REMOVE	1	0	0	0	0
675+77.9	LT	49.2	14		REMOVE	0	1	0	0	0
675+80.9	LT	54.4	16		REMOVE	0	1	0	0	0
675+87.2	LT	46.9	16		REMOVE	0	1	0	0	0
675+89.5	LT	48.9	14		REMOVE	0	1	0	0	0
675+95.5	LT	50.2	14		REMOVE	0	1	0	0	0
675+99.5	LT	50.0	16		REMOVE	0	1	0	0	0
676+01.4	LT	50.0	10		REMOVE	1	0	0	0	0
676+05.3	LT	53.1	14		REMOVE	0	1	0	0	0
676+06.9	LT	49.7	8		REMOVE	1	0	0	0	0
676+09.3	LT	49.3	16		REMOVE	0	1	0	0	0
676+17.1	LT	49.4	12		REMOVE	1	0	0	0	0
676+20.3	LT	49.7	14		REMOVE	0	1	0	0	0
676+21.1	LT	54.6	12		REMOVE	1	0	0	0	0
676+21.6	LT	51.9	14		REMOVE	0	1	0	0	0
676+34.3	LT	49.0	16		REMOVE	0	1	0	0	0
676+34.3	LT	52.7	14		REMOVE	0	1	0	0	0
676+37.0	LT	47.4	12		REMOVE	1	0	0	0	0
676+46.3	LT	50.7	12		REMOVE	1	0	0	0	0
676+48.1	LT	48.4	14		REMOVE	0	1	0	0	0
676+54.9	LT	52.1	12		PROTECT	0	0	0	0	1
676+55.5	LT	49.0	14		REMOVE	0	1	0	0	0
676+62.2	LT	50.4	18		PROTECT	0	0	0	0	1
676+71.6	LT	51.3	14		PROTECT	0	0	0	0	1
676+71.8	LT	49.3	14		REMOVE	0	1	0	0	0
676+81.3	LT	49.1	14		REMOVE	0	1	0	0	0
676+87.5	LT	48.8	24		REMOVE	0	1	0	0	0
676+95.7	LT	49.1	24	STUMP	REMOVE	0	1	0	0	0
677+19.6	LT	48.6	18		REMOVE	0	1	0	0	0
677+28.6	LT	52.2	14		PROTECT	0	0	0	0	1
677+33.2	LT	51.1	12		PROTECT	0	0	0	0	1
677+34.7	LT	50.0	16		PROTECT	0	0	0	0	1
677+51.1	LT	47.2	14		REMOVE	0	1	0	0	0
677+53.7	LT	48.9	14		REMOVE	0	1	0	0	0

TREE REMOVAL AND MAINTENANCE SCHEDULE

						20100110	20100210	20101000	20101300	20101350
STATION	OFFSET	SIZE-DIA. INCHES (SURVEY)	SIZE-DIA. INCHES (START OF CNSTRCTN)	TYPE	ACTION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TEMPORARY FENCE (FOOT)	TREE PRUNING (1 TO 10 INCH DIAMETER) (EACH)	TREE PRUNING (OVER 10 INCH DIAMETER) (EACH)
677+59.9	LT	45.9	18		REMOVE	0	1	0	0	0
677+61.6	LT	47.4	12		REMOVE	1	0	0	0	0
677+73.4	LT	48.0	24		REMOVE	0	1	0	0	0
678+25.4	LT	50.4	40		PROTECT	0	0	17	0	1
678+46.8	LT	47.2	16		PROTECT	0	0	17	0	1
678+49.5	LT	48.0	20		PROTECT	0	0	17	0	1
					TOTALS	109	57	231	6	26

FILE NAME =

USER NAME = .USER.

DESIGNED - JWB

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS
SCHEDULES

F.A.P.
RTE.

SECTION

COUNTY

TOTAL
SHEETS

SHEET
NO.

311

(1-IN TS

KENDALL

92

17

CONTRACT NO. 66955
ILLINOIS FED. AID PROJECT

SCALE: N.T.S.

SHEET NO. OF SHEETS