

p:\jobs\2007\20073028-08\cad\site\dm\00_0366955-snt-schedule-03.dgn
3/31/2011 12:05:43 PM

EARTHWORK SCHEDULE																			
		20200100												20400800					
		EARTH EXCAVATION			EXCAVATION AVAILABLE TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE (SHRINKAGE FACTOR = 15%)			EMBANKMENT			EARTHWORK BALANCE: WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (SHRINKAGE FACTOR = 15%)			WASTE HAUL OFF (SWELL FACTOR 15%)		
FROM	TO	CU YD			CU YD			CU YD			CU YD			CU YD			CU YD		
STATION	STATION	STAGE 1	STAGE 2	STAGE 2+	STAGE 1	STAGE 2	STAGE 2+	STAGE 1	STAGE 2	STAGE 2+	STAGE 1	STAGE 2	STAGE 2+	STAGE 1	STAGE 2	STAGE 2+	STAGE 1	STAGE 2	STAGE 2+
ILLINOIS 71																			
661+50	662+00	5	0	0	4	0	0	2	0	0	2	0	0	0	0	0	2	0	0
662+00	662+30	12	0	0	10	0	0	1	0	0	9	0	0	0	0	0	10	0	0
662+30	662+50	9	0	0	7	0	0	1	0	0	6	0	0	0	0	0	7	0	0
662+50	662+69	9	0	0	7	0	0	1	0	0	6	0	0	0	0	0	7	0	0
662+69	663+00	15	0	0	13	0	0	0	0	0	13	0	0	0	0	0	15	0	0
663+00	663+50	14	0	0	11	0	0	1	0	0	10	0	0	0	0	0	12	0	0
663+50	664+00	10	0	0	8	0	0	3	0	0	5	0	0	0	0	0	6	0	0
664+00	664+50	9	0	3	8	0	2	5	0	3	3	0	0	0	0	0	3	0	0
664+50	665+00	65	74	4	56	62	4	4	12	6	52	51	-2	0	0	2	61	59	0
665+00	665+15	30	46	0	25	39	0	0	7	1	25	32	-1	0	0	1	30	38	0
665+15	665+50	88	106	0	75	90	0	0	16	3	75	74	-3	0	0	4	88	87	0
665+50	666+00	152	91	1	129	78	1	3	27	8	127	50	-7	0	0	9	149	59	0
666+00	666+50	108	42	1	91	36	1	5	53	11	86	-16	-10	0	19	12	102	0	0
666+50	667+00	71	26	1	60	22	0	3	90	7	57	-68	-6	0	80	7	67	0	0
667+00	667+07	9	3	0	8	3	0	0	16	0	8	-13	0	0	15	0	9	0	0
667+07	667+50	41	17	0	35	14	0	62	100	0	-26	-86	0	31	101	1	0	0	0
667+50	668+00	47	15	0	40	13	0	105	112	0	-65	-99	0	76	116	0	0	0	0
668+00	668+16	30	5	0	25	4	0	19	24	0	7	-19	0	0	23	0	8	0	0
668+16	668+50	51	18	0	44	15	0	69	45	0	-26	-30	0	30	35	0	0	0	0
668+50	669+00	27	24	0	23	21	0	151	105	0	-128	-85	0	151	100	1	0	0	0
669+00	669+50	26	21	0	22	18	0	185	101	1	-162	-82	-1	191	97	1	0	0	0
669+50	670+00	26	43	0	22	37	0	177	40	1	-155	-4	-1	182	4	1	0	0	0
670+00	670+50	53	29	0	45	25	0	96	0	1	-51	25	-1	60	0	1	0	29	0
670+50	671+00	84	0	0	71	0	0	30	0	0	41	0	0	0	0	0	49	0	0
671+00	671+50	104	0	0	89	0	0	5	0	0	84	0	0	0	0	0	99	0	0
671+50	672+00	129	0	0	109	0	0	1	0	0	108	0	0	0	0	0	127	0	0
672+00	672+50	111	0	0	95	0	0	2	0	0	92	0	0	0	0	0	109	0	0
672+50	673+00	42	9	0	36	8	0	1	0	0	35	8	0	0	0	0	41	9	0
673+00	673+50	0	73	0	0	62	0	0	1	0	0	61	0	0	0	0	0	72	0
673+50	674+00	19	69	0	16	59	0	15	2	0	2	56	0	0	0	0	2	66	0
674+00	674+50	37	17	0	31	14	0	43	4	0	-12	10	0	14	0	0	0	12	0
674+50	675+00	56	27	0	48	23	0	49	4	0	-1	19	0	1	0	0	0	22	0
675+00	675+50	76	38	0	65	33	0	36	3	0	29	30	0	0	0	0	34	35	0
675+50	676+00	69	55	0	58	46	0	37	2	0	21	44	0	0	0	0	25	52	0
676+00	676+50	65	76	0	55	64	0	37	2	0	18	62	0	0	0	0	22	73	0
676+50	677+00	66	91	0	56	77	0	27	1	0	29	76	0	0	0	0	34	90	0
677+00	677+50	60	79	0	51	67	0	25	1	0	27	67	0	0	0	0	32	78	0
677+50	678+00	62	47	0	53	40	0	13	1	0	40	39	0	0	0	0	47	46	0
678+00	678+05	6	3	0	5	2	0	0	0	0	5	2	0	0	0	0	6	3	0
678+05	678+50	43	24	0	37	20	0	5	0	0	32	20	0	0	0	0	38	24	0
678+50	679+00	12	37	0	10	31	0	5	0	0	5	31	0	0	0	0	6	37	0
679+00	679+19	0	23	0	0	19	0	0	0	0	0	19	0	0	0	0	0	23	0
679+19	679+50	0	40	0	0	34	0	0	0	0	0	34	0	0	0	0	0	40	0
679+50	680+00	0	50	0	0	42	0	0	1	0	0	42	0	0	0	0	0	49	0
680+00	680+50	0	37	0	0	32	0	0	0	0	0	31	0	0	0	0	0	37	0
680+50	681+00	10	16	0	9	13	0	0	0	0	9	13	0	0	0	0	10	16	0
681+00	681+50	20	0	0	17	0	0	0	0	0	17	0	0	0	0	0	20	0	0
681+50	682+00	19	0	0	17	0	0	0	0	0	17	0	0	0	0	0	19	0	0
682+00	682+16	6	0	0	5	0	0	0	0	0	5	0	0	0	0	0	6	0	0
682+16	682+50	13	0	0	11	0	0	0	0	0	11	0	0	0	0	0	13	0	0
682+50	682+73	17	0	0	14	0	0	0	0	0	14	0	0	0	0	0	17	0	0
682+73	683+00	22	0	0	18	0	0	0	0	0	18	0	0	0	0	0	22	0	0
683+00	683+50	13	0	0	11	0	0	0	0	0	11	0	0	0	0	0	13	0	0
683+50	684+00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
684+00	684+50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

FILE NAME =	USER NAME = .USER.	DESIGNED - JWB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000 ' / IN.	DRAWN - JWB	REVISED -					311	(1-1)N TS	KENDALL	92	18
	PLOT DATE = 3/31/2011	CHECKED - RS	REVISED -					CONTRACT NO. 66955				
	DATE - 03/31/2011	REVISED -	SCALE: N.T.S.					SHEET NO. OF SHEETS	ILLINOIS FED. AID PROJECT			