

h:\jobs2007\20073028-08\cd\ashe\dgn\00\1D366955-ent-schedule-06.dgn
3/31/2011 12:05:55 PM

PERMANENT PAVEMENT MARKING SCHEDULE

LOCATION			78000200	78000400	78000500	78000600	78004200	78004280	78100100			78300100	78300200
			THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER			PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	TO	STATION	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(FT)	ONE-WAY AMBER (EACH)	ONE-WAY CRYSTAL (EACH)	TWO-WAY AMBER (EACH)	(SQ FT)	(EACH)
ILLINOIS 71													
661+00		666+00	1251	104	0	0	0	0	0	0	6	556	5
666+00		671+00	2502	42	40	65	0	0	16	0	8	748	6
671+00		674+00	1184	0	294	22	94	109	0	9	16	741	2
674+00		680+00	3355	0	263	45	47	0	26	2	4	836	8
680+00		684+00	1503	0	23	0	0	0	2	0	10	488	5
VAN EMMON													
50+00		56+00	2043	0	0	6	0	0	6	0	10	800	0
56+00		60+00	2182	0	146	34	16	0	14	4	8	533	0
TOTALS			14020	146	765	172	156	109	64	15	62	4,703	26

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION			70300100	70300210	70300220	70300250	70300280	70301000
			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE, 4"	TEMPORARY PAVEMENT MARKING - LINE, 8"	TEMPORARY PAVEMENT MARKING - LINE, 24"	WORK ZONE PAVEMENT MARKING REMOVAL
STATION	TO	STATION	(FT)	(SQ FT)	(FT)	(FT)	(FT)	(SQ FT)
ILLINOIS 71								
661+00		666+00	183	0	1668	0	0	617
666+00		671+00	222	0	2000	18	0	753
671+00		674+00	172	62	1336	216	14	737
674+00		680+00	278	16	2403	126	0	994
680+00		684+00	161	0	1468	0	0	543
VAN EMMON								
50+00		56+00	198	0	1801	0	0	666
56+00		60+00	190	0	1725	0	0	638
TOTALS			1,405	78	12,401	361	14	4,949

PERMANENT SIGNING SCHEDULE

LOCATION			72000100			72000200			73000100
			SIGN PANELS, TYPE 1			SIGN PANELS, TYPE 2			WOOD SIGN SUPPORT
			R2-1	R2-1	TRAFFIC SIGNAL MAST ARM	W14-3	TRAFFIC SIGNAL MAST ARM	TRAFFIC SIGNAL MAST ARM	(FT)
			30" x 36"	30" x 36"	5' x 1.5'	48" x 60"	5.5' x 2.5'	6.5' x 2.5'	
			SPEED LIMIT 50	SPEED LIMIT 55	ILLINOIS 71	NO PASSING ZONE	VAN EMMON ROAD	RESERVATION ROAD	
*	661+83	LT				20			28
*	661+83	LT		7.5					
	661+83	RT	7.5						13
	663+66	LT	7.5						13
	663+66	RT		7.5					13
**	672+18	LT					27.5		
	672+59	RT			7.5				
	673+28	LT			7.5				
**	673+48	RT						32.5	
Totals:			15	15	15	20	27.5	32.5	67
* SHARED SIGN SUPPORT									
** TWO SIGNS REQUIRED, TOTAL SF SHOWN									

FILE NAME =	USER NAME = .USER..	DESIGNED - JWB	REVISED -
		DRAWN - JWB	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - RS	REVISED -
	PLOT DATE = 3/31/2011	DATE - 03/31/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 311 (IL 71) AT VAN EMMON / RESERVATION ROADS SCHEDULES			
SCALE: N.T.S.	SHEET NO.	OF	SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)N TS	KENDALL	92	21
CONTRACT NO. 66955				
ILLINOIS FED. AID PROJECT				