

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS
				100% STATE
				ROADWAY
				0005
				RURAL
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	857	857
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15
40603520	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	612	612
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	300	300
42400800	DETECTABLE WARNINGS	SQ FT	40	40
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4755	4755
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	90	90
44000600	SIDEWALK REMOVAL	SQ FT	300	300
44213200	SAW CUTS	FOOT	2211	2211
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	88	88
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	141	141
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	652	652
44213100	PAVEMENT FABRIC	SQ YD	1034	1034
44213204	TIE BARS 3/4"	EACH	1163	1163
44201299	DOWEL BARS 1 1/2"	EACH	1074	1074
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	19	19
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	90	90
63500105	DELINEATORS	EACH	80	80
67100100	MOBILIZATION	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9.2	9.2
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3208	3208
Z0037310	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	152	152

*SPECIALITY ITEMS

FILE NAME =	USER NAME = petelyj	DESIGNED - RON WOODSHANK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pvc\work\pwidot\petelyj\02257878\0366	21-shr-details.DGN	DRAWN - RON WOODSHANK	REVISED -		80	06-41RA-5	BUREAU	10	3			
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -		SCALE: _____	SHEET NO. 1 OF 1 SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 66B21				
	PLOT DATE = 4/21/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							