

SCHEDULE - PAVEMENT PATCHING								
LOCATION	CLASS B PATCHING TYPE II 10"	CLASS B PATCHING TYPE III 10"	CLASS B PATCHING TYPE IV 10"	PAVEMENT PATCHING (FULL DEPTH)	DOWEL BARS	SAW CUTS	PAVEMENT FABRIC	TIE BARS
	SO YD	SO YD	SO YD	SO YD	EACH	FEET	SO YD	EACH
TRUCK PARKING LOT								
P1			26		26	60	26	26
P2	5				3	22	5	20
P3		19			26	53	19	20
P4	6				7	16	6	20
P5			38		13	54	38	15
P6	12				15	18	12	22
P7			31		29	67	31	30
P8	15				19	33	15	22
P9		25			28	44	25	24
P10	9				8	20	9	24
P11		22			18	54	22	31
P12			28		28	64	28	28
P13	15				13	38	15	30
P14		21			23	55	21	25
P15			27		28	62	27	26
P16			27		28	62	27	26
P17			29		28	64	29	28
P18			28		28	64	28	28
P19		17			28	35	17	16
P20			28		28	48	28	28
P21			28		28	48	28	28
P22			28		28	48	28	28
P23		20			18	38	20	28
P24			27		28	62	27	26
P25			26		26	62	26	24
P26			26		26	49	26	24
P27			25		28	60	25	24
P28			25		28	46	25	24
P29			23		28	58	23	22
P30			25		28	28	25	24
P31			23		26	58	23	22
P32			25		28	30	25	24
P33			23		26	46	23	22
P34			30		28	66	30	30
P35			30		28	49	30	30
P36		18			24	52	18	21
P37			26		28	61	26	26
P38	15				10	66	15	44
P39	11				28	28	11	8
CAR PARKING LOT				152	158	325	152	195
TOTAL	88	141	652	152	1074	2211	1034	1163

SCHEDULE - PAVEMENT MARKING			
LOCATION	EPOXY PAVEMENT MARKING L & S	EPOXY PAVEMENT MARKING LINE 4"	
	SO FT	FEET	
	WHITE	YELLOW	WHITE
STA. 691+95 TO STA. 700+00		808	390
CAR PARKING (ENTRANCE)			318
CAR PARKING LOT			1312
HANDICAP PARKING	9.2		380
SUBTOTAL	9.2	808	2400
TOTAL	9.2	3208	

SCHEDULE - DELINEATORS		
LOCATION		DELINEATORS
STA.	TO STA.	EACH
STA. 691+95	TO STA. 700+00	80
TOTAL		80

SCHEDULE - AGG WEDGE SHLD TYPE B		
LOCATION		TONS
STA.	TO STA.	
STA. 691+95	TO STA. 695+82	8
STA. 695+82	TO STA. 700+00	8
STA. 695+82	TO STA. 500+00	3
TOTAL		19

SCHEDULE - HMA RESURFACING				
LOCATION	HMA SURFACE REMOVAL 1 1/2"	MIXTURE FOR CRACKS JOINT AND FLANGWAYS	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HMA SURFACE CSE. MIX C. N90
	SO YD	TON	GAL	TON
STA. 691+95 TO STA. 700+00	2348	5	423	394
CAR PARKING (ENTRANCE)	382	5	69	48
CAR PARKING LOT	2025	5	365	170
TOTAL	4755	15	857	612

SCHEDULE - HANDICAP PARKING						
LOCATION	COMBINATION CURB & GUTTER REMOVAL	COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24	SIDEWALK REMOVAL	PORTLAND CEMENT CONCRETE SIDEWALK 5"	DETECTABLE WARNINGS	TIE BARS 3/4"
	FOOT	FOOT	EACH	EACH	SO FT	EACH
HANDICAP PARKING	90	90	300	300	40	36
TOTAL	90	90	300	300	40	36