

SUMMARY OF QUANTITIES			URBAN	STP	HSIP		HSIP	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
				0004 ROADWAY 80% FED 20% STATE	0004 RDWY 90% FED 10% STATE	0021 SAFETY 100% CITY	0021 SAFETY 90% FED 7.5% STATE 2.5% CITY	0021 SAFETY 90% FED 5.0% STATE 5.0% CITY
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	691				361	330
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	10				5	5
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2				1	1
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	2620			2362	76	182
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2266				1056	1210
82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL PHOTO-CELL CONTROL, 400 WATT MOUNT,	EACH	11			11		
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2					2
85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1				1	
86000105	MASTER CONTROLLER (SPECIAL)	EACH	1				1	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4782				1820	2962
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4899				2502	2397
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	3458.5				1391.5	2067
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1					1
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1					1
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1					1
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1					1
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	3					3
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1				1	
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1					1
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	3				3	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7				3.5	3.5
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10					10
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	69				15	54
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	63				63	
87900100	DRILL EXISTING FOUNDATION	EACH	1					1
87900200	DRILL EXISTING HANDHOLE	EACH	5					5

*SPECIALTY ITEMS

FILE NAME D468877-CADD.dgn	USER NAME = bergsekerse	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/3/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
LOCUST STREET-RECONSTRUCTION

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685/22	(41Z, 135) R.N. (ICS) I	FULTON	125	6C
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 68877	
			D4-94-009-09	