

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		FED - STA 90% - 10% 0003		
20200100	EARTH EXCAVATION	CU YD	876	876		
20400800	FURNISHED EXCAVATION	CU YD	1560	1560		
20800150	TRENCH BACKFILL	CU YD	9	9		
21101615	TOPSOIL FURNISH ^{AND} PLACE, 4"	SQ YD	4786	4786		
25000200	SEEDING, CLASS 2	ACRE	1.6	1.6		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	144	144		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	144	144		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	144	144		
25100105	MULCH, METHOD 1	ACRE	1.6	1.6		
25100630	EROSION CONTROL BLANKET	SQ YD	270	270		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	320	320		
28000305	TEMPORARY DITCH CHECKS	FOOT	288	288		
28000400	PERIMETER EROSION BARRIER	FOOT	2294	2294		
28000500	INLET AND PIPE PROTECTION	EACH	6	6		
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	49	49		
28200200	FILTER FABRIC	SQ YD	49	49		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	3082	3082		
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	2889	2889		
35501310	HOT - MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD	910	910		
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	4.5	4.5		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200		
40600990	TEMPORARY RAMP	SQ YD	66.7	66.7		
40603535	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	724	724		
44000100	PAVEMENT REMOVAL	SQ YD	874	874		
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	4622	4622		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		FED - STA 90% - 10% 0003		
44004000	PAVED DITCH REMOVAL	FOOT	60	60		
44004250	PAVED SHOULDER REMOVAL	SQ YD	463	463		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1742	1742		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	841	841		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	929	929		
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	520	520		
48203100	HOT - MIX ASPHALT SHOULDERS	TON	83	83		
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3		
54213663	PRECAST REINFORCED ^{CONCRETE} FLARED END SECTIONS 18"	EACH	1	1		
54214515	PRECAST REINFORCED ^{CONCRETE FLARED} END SECTIONS, ^{EQUIVALENT} ROUND-SIZE 30"	EACH	1	1		
54248510	CONCRETE COLLAR	CU YD	1.7	1.7		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	8	8		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	40	40		
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	8	8		
60605000	COMBINATION ^{CONCRETE} CURB AND GUTTER, TYPE B-6.24	FOOT	65	65		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	119.2	119.2		
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	6	6		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	21	21		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	364	364		

* SPECIALTY ITEMS

FILE NAME D:\68993-ah-500.dgn	USER NAME = hude1sor	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 318	SECTION 4W-2, RS-3	COUNTY PEORIA	TOTAL SHEETS 37	SHEET NO. 4	
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -			CONTRACT NO. 68993					
	PLOT DATE = 3/14/2011	CHECKED -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
		DATE -	REVISED -								