

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Cleaning & painting of the existing steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All beams, bearings, and all other structural steel shall be cleaned per Near White Blast Cleaning – SSPC SP 10 according to the following schedule.

Bridge 1 & 2 Entire Structure, excluding all steel previously metalized within 5ft from the beam ends.

The designated paint system shall be **Paint System 1 OZ/EU**
The final finish coat for the interior and exterior shall be according to the following schedule:

Bridge 1 & 2 Paint system 1 shall be used and all exterior fascias including the bottom of the bottom flanges shall be blue (Munsell No. 10B 36). All of the underside shall be painted Light Gray (Munsell No. 5B 7/1).

QP1 SHALL BE REQUIRED FOR THIS CONTRACT.

AIR MONITORS – None for this project

FILE NAME = June 17 2011.dgn	USER NAME = inglistj	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		F.A. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2.0000' / IN.	CHECKED -	REVISED -	REVISED -		1-155	D4 BRIDGE PAINTING 2011	TAZEWELL	10	2		
PLOT DATE = 3/3/2011	DATE -	REVISED -	REVISED -		CONTRACT NO. 68A39						
							ILLINOIS FED. AID PROJECT				