

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	LOCATION OF WORK:				
			DEWITT CO. F.A.P. 760 ILL 48 S.N. 020-8033 LOCATION 1 RURAL 100% STATE CONSTRUCTION TYPE CODE: 0014	DEWITT CO. F.A.P. 760 ILL 48 S.N. 020-8034 LOCATION 2 RURAL 100% STATE 0014	MC LEAN CO. F.A.P. 71 ILL 54 S.N. 057-8003 LOCATION 3 RURAL 100% STATE 0014	MC LEAN CO. F.A.P. 730 US 51 S.N. 057-8194 LOCATION 4 URBAN 100% STATE 0014	
			TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
44000177	HOT MIX ASPHALT SURFACE REMOVAL, 7"	SQ YD	25.3	25.3			
44000186	HOT MIX ASPHALT SURFACE REMOVAL, 9"	SQ YD	43.2			43.2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.2	4.9	7.1	10.8	9.4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10,670.0	1,270.0	2,080.0	4,900.0	2,420.0
50800515	BAR SPLICERS	EACH	122.0	15.0	32.0	45.0	30.0
67100100	MOBILIZATION	L SUM	1.0	0.2	0.2	0.2	0.4
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	3.0	1.0	1.0	1.0	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0				1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	28.0	7.0	7.0	7.0	7.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	3.0	1.0	1.0	1.0	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	200.0	50.0	50.0	50.0	50.0
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	79.8		31.8		48.0

• ROUTES VARIOUS
 ** POSTING MITIGATION FY2011-1
 *** DEWITT / MCLEAN

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pw\work\pwidat\keysrb\d0248870\05788914-sht-over.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	***	23	4
		CHECKED -	REVISED -		CONTRACT NO. 70894								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								