

3:51:37 PM

Mar-25-2011 03:51:37PM

\$FILE\$

CONTRACT NO. 72667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

80% FEDERAL 20% STATE  
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE															
					0001 ROADWAY	0008 STRUCTURE														
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	299	299															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	534	534															
20100500	TREE REMOVAL, ACRES		ACRE	18.9	18.9															
20200100	EARTH EXCAVATION	.	CU YD	550503	550503															
20200200	ROCK EXCAVATION		CU YD	100	100															
20200500	EARTH EXCAVATION (WIDENING)	.	CU YD	<b>130</b>	<b>130</b>															
20400800	FURNISHED EXCAVATION		CU YD	514850	514850															
20700220	POROUS GRANULAR EMBANKMENT		CU YD	40	40															
20800150	TRENCH BACKFILL		CU YD	4665	4665															
21101615	TOPSOIL FURNISH AND PLACE, 4"		SO YD	877140	877140															
21400100	GRADING AND SHAPING DITCHES	.	FOOT	500	500															
* 25000200	SEEDING, CLASS 2		ACRE	230	230															
* 25000350	SEEDING, CLASS 7		ACRE	40	40															
* 25000400	NITROGEN FERTILIZER NUTRIENT		POUND	20700	20700															
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	20700	20700															
* 25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	20700	20700															
* 25000700	AGRICULTURAL GROUND LIMESTONE		TON	460	460															
* 25003200	INTERSEEDING, CLASS 2		ACRE	10	10															
* 25100115	MULCH, METHOD 2		ACRE	270	270															
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET		SO YD	7197	7197															
28000200	EARTH EXCAVATION FOR EROSION CONTROL		CU YD	1000	1000															
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	75000	75000															
28000400	PERIMETER EROSION BARRIER		FOOT	7000	7000															
28000500	INLET AND PIPE PROTECTION		EACH	80	80															
28001000	AGGREGATE (EROSION CONTROL)		TON	1500	1500															
28100707	STONE DUMPED RIPRAP, CLASS A4	.	SO YD	19885	19885															
28100709	STONE DUMPED RIPRAP, CLASS A5	.	SO YD	426	426															

\*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
FAP 310 (US 67/IL 104)  
SHEET 1 OF 13

DATE 10/2010  
DRAWN BY BGJ  
CHECKED BY EBB