

3:51:38 PM

Mar-25-2011 03:51:38PM

\$FILES

CONTRACT NO. 72667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE						
					0001 ROADWAY	0008 STRUCTURE					
48101200	AGGREGATE SHOULDERS, TYPE B		TON	26325	26325						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"		SQ YD	7730	7730						
48203100	HOT-MIX ASPHALT SHOULDERS		TON	294	294						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"		SQ YD	111158	111158						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	.	EACH	1	1						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	.	EACH	1	1						
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	.	EACH	1	1						
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	.	EACH	1	1						
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	.	EACH	1	1						
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	.	EACH	1	1						
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	.	EACH	1	1						
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	.	EACH	1	1						
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	.	EACH	1	1						
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	.	EACH	1	1						
50105220	PIPE CULVERT REMOVAL	.	FOOT	4930	4930						
50200100	STRUCTURE EXCAVATION		CU YD	214.1		214.1					
50300225	CONCRETE STRUCTURES		CU YD	240.6		240.6					
50300255	CONCRETE SUPERSTRUCTURE		CU YD	721.4		721.4					
50300260	BRIDGE DECK GROOVING		SO YD	1634		1634					
50300280	CONCRETE ENCASEMENT		CU YD	14.2		14.2					
50300300	PROTECTIVE COAT		SO YD	2141		2141					
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.		FOOT	2200		2200					
50800105	REINFORCEMENT BARS		POUND	90670		90670					
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	189300		189300					
50800515	BAR SPLICERS		EACH	138		138					
51100100	SLOPE WALL 4 INCH		SO YD	713		713					
51201610	FURNISHING STEEL PILES HP12X63		FOOT	1968		1968					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 310 (US 67/IL 104)
 SHEET 4 OF 13
 DRAWN BY B G J
 CHECKED BY E B B
 DATE 10/2010