

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	30
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

AGGREGATE SHOULDERS, TYPE B

48101200

LOCATION	SIDE	TON
FAP 310 (US 67)	LT IS	4568.2
	LT OS	2504.7
	RT IS	4547.2
	RT OS	2417.9
RAMP A	RT	848.8
	LT	436.9
RAMP B	RT	684.6
	LT	394.2
RAMP C	RT	789.0
	LT	336.6
RAMP D	RT	701.7
	LT	429.2
CONCORD ROAD	RT	662.6
	LT	671.8
EX US 67 / IL 104	RT	111.1
	LT	114.8
US 67 FRONTAGE ROAD (CONCORD)	RT	944.3
	LT	987.5
SERVICE DRIVE 81	RT	6.7
	LT	6.2
COOPER STREET	RT	33.7
	LT	29.5
NEW STREET	RT	140.6
	LT	140.8
RELOCATED CREWS LANE	RT	207.1
	LT	193.3
ASH STREET	RT	18.8
	LT	23.5
US 67 FRONTAGE ROAD (BETHEL)	RT	215.1
	LT	214.8
BETHEL LANE	RT	139.0
	LT	130.9
SERVICE DRIVE 91	RT	30.6
	LT	30.9
RELOCATED CYLINDER HEAD ROAD	RT	176.0
	LT	131.6
OLD CYLINDER HEAD ROAD	RT	48.0
	LT	52.9
GILLILAND ROAD CONNECTOR	RT	24.5
	LT	27.4
GILLILAND ROAD EXTENSION	RT	95.0
	LT	82.0
ST. PAUL'S CHURCH ROAD	RT	69.4
	LT	82.6
SERVICE DRIVE 92	RT	43.7
	LT	30.6
DUTCH LANE EAST	RT	128.3
	LT	125.6
DUTCH LANE WEST	RT	177.1
	LT	172.5
HART'S GRAVEL ROAD	RT	107.0
	LT	106.8
TEMPORARY ACCESS ROAD	RT	283.7
	LT	217.1
TRANSITION A	RT	75.9
	LT	27.9
TRANSITION B	RT	47.8
	LT	13.4
TRANSITION C	RT	85.4
	LT	31.4
TRANSITION D	RT	33.7
	LT	63.9
TOTAL		26324.2
USE		26325

PCC SIDEWALK 4 INCH

42400100

STATION TO STATION	SIDE	WIDTH	SO FT
COOPER STREET			
444+03.0	444+13.0	RT	4
444+25.0	445+49.5	RT	4
TOTAL			538.0
USE			538

REMOVAL OF EXISTING STRUCTURES

PAY ITEM NO.	STATION	SIDE	OFFSET	DESCRIPTION	EACH
FAP 310 (US 67)					
50100300	868+60.0	RT	117.3	WOOD BRIDGE W/ CONC/STONE WALLS	1
50100400	894+88.0	LT	187.2	2' X 2' CONC BOX CULVERT	1
50100500	967+99.0	LT	51.1	2' X 2' CONC BOX CULVERT	1
50100600	974+64.2	RT	17.0	2' X 2' CONC BOX CULVERT	1
50100700	979+13.2	LT	22.4	4' X 4' CONC BOX CULVERT	1
50100800	994+89.9	RT	91.7	6' X 3' CONC BOX CULVERT	1
50100900	1019+24.3	RT	90.7	6' X 4' CONC BOX CULVERT	1
COOPER STREET					
50101000	444+90.3	RT	8.6	6' X 6' CONC BOX CULVERT W/ CMP EXTENSION	1
RELOCATED CYLINDER HEAD ROAD					
50101100	95+86.3	LT	45.1	ROOT CELLAR	1
DUCTH LANE EAST					
50101200	140+02.3	LT	6.7	2' X 2' CONC BOX CULVERT	1

* TRENCH BACKFILL REQUIRED - 21.1 CU YD

BUILDING REMOVAL SCHEDULE

PAY ITEM NO.	STATION	SIDE	OFFSET	DESCRIPTION	EACH
FAP 310 (US 67)					
Z0007601	886+43.4	LT	0.6	METAL GRAIN BIN	1
Z0007602	887+12.2	LT	46.3	METAL GRAIN BIN	1
Z0007603	887+16.7	LT	24.7	METAL GRAIN BIN	1
Z0007604	887+20.8	LT	3.9	METAL GRAIN BIN	1
Z0007605	887+25.9	RT	17.3	METAL GRAIN BIN	1
Z0007606	924+22.6	RT	152.8	BARN	1
Z0007607	929+72.8	RT	6.1	1 STORY HOUSE	1
Z0007608	930+30.1	RT	137.9	BARN	1
Z0007609	930+82.7	RT	60.0	GARAGE	1

3:57:13 PM

Mar-25-2011 03:57:13PM

\$FILE\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 310 (US 67/IL 104)
 SHEET 14 OF 42

DATE 10/10
 DRAWN BY EBB
 CHECKED BY