CONTRACT NO. 72667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	41
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE

60107600			60108100			60100060	78001110
EASTBOUND INSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO		
		FOOT		FOOT	STRUCT NO	EACH	FOOT
FAP 310 (US 67)							
770+00	772+50	250.0	770+00	14.6		1	2.0
772+50	775+00	250.0	772+50	14.6		1	2.0
775+00	777+50	250.0	775+00	14.6		1	2.0
777+50	780+05	255.0	777+50	14.6		1	2.0
800+00	802+50	250.0	800+00	14.6		1	2.0
802+50	806+00	350.0	802+50	15.3		1	2.0
806+00	809+50	350.0	806+00	15.3		1	2.0
809+50	812+00	250.0	809+50	14.6		1	2.0
812+00	814+50	250.0	812+00	14.6		1	2.0
814+50	817+00	250.0	814+50	14.6		1	2.0
817+00	819+50	250.0	817+00	14.6		1	2.0
819+50	822+00	250.0	819+50	14.6		1	2.0
822+00	824+50	250.0	822+00	14.6		1	2.0
824+50	827+00	250.0	824+50	14.6		1	2.0
827+00	829+50	250.0	827+00	14.6		1	2.0
829+50	831+60	210.0	829+50	15.4		1	2.0
831+60	834+00	240.0	834+00	15.4		1	2.0
834+00	839+00	500.0	839+00	12.9		1	2.0
839+00	843+91	491.0	843+91	12.9		1	2.0
843+91	849+00	509.0	849+00	13.9		1	2.0
849+00	851+00	200.0	851+00	15.1		1	2.0
851+00	854+00	300.0	851+00			1	
854+00	858+00	400.0	854+00	14.2		1	2.0
858+00	859+00	100.0	859+00	13.2		1	2.0
860+81	865+00	419.0	865+00	11.2		1	2.0
865+00	868+00	300.0	868+00	13.5		1	2.0
868+00	873+00	500.0	868+00			1	
873+00	878+00	500.0	873+00	12.9		1	2.0
878+00	882+00	400.0	878+00	12.9		1	2.0
882+00	886+73	473.0	882+00	11.8		1	2.0
888+44	893+00	456.0	888+44	11.8		1	2.0
893+00	894+49	149.0	893+00	10.4		1	2.0
913+46	915+00	154.0	915+00	14.1		1	2.0
915+00	920+00	500.0	920+00	12.9		1	2.0
920+00	921+42	142.0	921+42	13.5		1	2.0
921+42	926+81	539.0	921+42			1	
928+25	931+90	365.0	931+90	19.0	25		
931+90	936+00	410.0	931+90		25		
936+00	941+00	500.0	936+00	12.8		1	2.0
941+00	946+00	500.0	941+00	12.8		1	2.0
946+00	950+00	400.0	946+00	12.8		1	2.0
950+00	954+68	468.0	950+00	12.9		1	2.0
956+40	959+08	268.0	956+40	16.0	30		
959+08	963+00	392.0	963+00	12.9		1	2.0
963+00	968+00	500.0	968+00	12.9		1	2.0
968+00	971+03	303.0	971+03	12.9		1	2.0
971+03	974+78	375.0	971+03			1	
976+40	981+00	460.0	976+40		31		
981+00	985+47	447.0	981+00	12.9		1	2.0
985+47	989+00	353.0	989+00	13.9		1	2.0
989+00	992+07	307.0	992+07	12.9		1	2.0
992+07	997+79	572.0	992+07			1	
999+40	1004+00	460.0	999+40	16.0	39		
1004+00	1007+91	391.0	1004+00	11.0		1	2.0
1007+91	1012+00	409.0	1012+00	12.9		1	2.0
1012+00	1016+00	400.0	1016+00	12.9		1	2.0
1016+00	1019+08	308.0	1019+08	13.1		1	2.0
1019+08	1021+64	256.0	1019+08			1	
1032+41	1036+87	446.0	1036+87	12.9		1	2.0
1040+56	1043+50	294.0	1040+56	14.5		1	2.0
1043+50	1046+00	250.0	1046+00	13.3		1	2.0
1046+00	1050+00	400.0	1050+00	12.9		1	2.0
1050+00	1054+10	410.0	1054+10	12.9		1	2.0
1055+72	1060+00	428.0	1060+00	11.7		1	2.0
1060+00	1065+00	500.0	1065+00	12.9		1	2.0
1065+00	1070+00	500.0	1070+00	12.9		1	2.0
1070+00	1075+55	555.0	1075+55	12.9		1	2.0
1077+85	1082+85	500.0	1082+85	11.3		1	2.0
1082+85	1086+00	315.0	1086+00	12.9		1	2.0
1086+00	1088+93	293.0	1088+93	12.9		1	2.0
1102+00	1105+68	368.0	1102+00	11.6		1	2.0
1119+93	1125+25	532.0	1125+25	12.9		1	2.0
1126+99	1130+00	301.0	1130+00	15.0	62		
SUBTOTALS		26373.0		882.5		67	122.0

NOTE: MINIMUM SLOPE IS 0.30%

PIPE UNDERDRAIN SCHEDULE

60107600			60108100			60100060	78001110
WESTBOUND INSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO		
		FOOT		FOOT	STRUCT NO	EACH	FOOT
FAP 310 (US 67)							
764+85	768+69	384.0	764+85	15.5		1	2.0
800+00	802+50	250.0	800+00	14.6		1	2.0
802+50	806+00	350.0	802+50	15.3		1	2.0
806+00	809+50	350.0	806+00	15.3		1	2.0
809+50	812+00	250.0	809+50	14.6		1	2.0
812+00	814+50	250.0	812+00	14.6		1	2.0
814+50	817+00	250.0	814+50	14.6		1	2.0
817+00	819+50	250.0	817+00	14.6		1	2.0
819+50	822+00	250.0	819+50	14.6		1	2.0
822+00	824+50	250.0	822+00	14.6		1	2.0
824+50	827+00	250.0	824+50	14.6		1	2.0
827+00	829+50	250.0	827+00	14.6		1	2.0
829+50	831+60	210.0	829+50	15.4		1	2.0
831+60	834+00	240.0	834+00	15.4		1	2.0
834+00	839+00	500.0	839+00	12.9		1	2.0
839+00	843+91	491.0	843+91	12.9		1	2.0
843+91	849+00	509.0	849+00	13.9		1	2.0
849+00	851+00	200.0	851+00	15.6		1	2.0
851+00	854+00	300.0	851+00			1	
854+00	858+00	400.0	854+00	13.6		1	2.0
858+00	859+00	100.0	859+00	11.1		1	2.0
860+69	865+00	431.0	865+00	12.8		1	2.0
865+00	868+00	300.0	868+00	13.5		1	2.0
868+00	873+00	500.0	868+00			1	
873+00	878+00	500.0	873+00	12.9		1	2.0
878+00	881+00	300.0	878+00	13.3		1	2.0
881+00	886+43	543.0	881+00	12.1		1	2.0
888+44	893+00	456.0	888+44	12.9		1	2.0
893+00	898+00	500.0	893+00	12.2		1	2.0
898+00	903+00	500.0	898+00	12.9		1	2.0
903+00	908+00	500.0	903+00	12.9		1	2.0
908+00	913+00	500.0	908+00	14.9		1	2.0
913+00	918+00	500.0	918+00	14.9		1	2.0
918+00	921+42	342.0	921+42	13.5		1	2.0
921+42	926+81	539.0	921+42			1	
948+10	950+00	190.0	948+10	13.9		1	2.0
950+00	954+27	427.0	950+00	12.0		1	2.0
956+40	959+08	268.0	956+40	14.0		1	2.0
959+08	964+00	492.0	964+00	12.9		1	2.0
964+00	969+00	500.0	969+00	12.9		1	2.0
969+00	971+03	203.0	971+03	11.4		1	2.0
971+03	974+78	375.0	971+03			1	
989+17	992+07	290.0	992+07	12.9		1	2.0
992+07	997+79	572.0	992+07			1	
999+40	1004+00	460.0	999+40	12.9		1	2.0
1004+00	1007+91	391.0	1004+00	12.4		1	2.0
1007+91	1012+00	409.0	1012+00	12.9		1	2.0
1012+00	1016+00	400.0	1016+00	12.9		1	2.0
1016+00	1019+08	308.0	1019+08	13.1		1	2.0
1019+08	1023+00	392.0	1019+08			1	
1023+00	1026+00	300.0	1023+00	12.9		1	2.0
1026+00	1031+22	522.0	1026+00	11.6		1	2.0
1032+69	1036+87	418.0	1036+87	16.1		1	2.0
1036+87	1040+00	313.0	1036+87			1	
1040+00	1043+50	350.0	1040+00	13.2		1	2.0
1043+50	1046+00	250.0	1046+00	13.3		1	2.0
1046+00	1050+00	400.0	1050+00	11.7		1	2.0
1050+00	1054+10	410.0	1054+10	11.8		1	2.0
1055+72	1060+00	428.0	1060+00	12.9		1	2.0
1060+00	1065+00	500.0	1065+00	12.9		1	2.0
1065+00	1070+00	500.0	1070+00	11.9		1	2.0
1070+00	1075+55	555.0	1075+55	11.8		1	2.0
1077+47	1082+85	538.0	1082+85	12.9		1	2.0
1082+85	1086+00	315.0	1086+00	12.9		1	2.0
1086+00	1091+60	560.0	1091+60	12.9		1	2.0
1091+60	1094+00	240.0	1091+60			1	
1094+00	1099+41	541.0	1094+00	11.2		1	2.0
1102+00	1107+00	500.0	1102+00	12.9		1	2.0
1107+00	1112+00	500.0	1107+00	12.9		1	2.0
1112+00	1113+80	180.0	1112+00	13.4		1	2.0
1113+80	1116+00	220.0	1116+00	13.6		1	2.0
1116+00	1120+72	472.0	1120+72	12.9		1	2.0
1120+72	1125+25	453.0	1125+25	11.8		1	2.0
1131+62	1133+60	198.0	1133+60		63		
SUBTOTALS		28035.0		868.8		73	130.0

NOTE: MINIMUM SLOPE IS 0.30%

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP 310 (US 67/IL 104)
SHEET 25 OF 42

DRAWN BY EBB

DATE 10/10 CHECKED BY

Mar-25-2011 03:57:18PM

$FILE$