

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	42
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE
60107600 60108100 60100060 78001110

WESTBOUND OUTSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCT NO	EACH	FOOT
FAP 310 (US 67)							
786+50	789+00	250.0	786+50	18.1		1	2.0
789+00	789+58	57.7	789+00	19.3		1	2.0
793+62	799+50	588.0	793+62		2		
799+50	802+00	250.0	799+50	18.1		1	2.0
802+00	804+50	250.0	802+00	18.1		1	2.0
804+50	807+00	250.0	804+50	18.1		1	2.0
807+00	809+50	250.0	807+00	18.1		1	2.0
809+50	812+00	250.0	809+50	18.1		1	2.0
812+00	816+00	400.0	812+00	19.1		1	2.0
816+00	820+82	482.0	816+00	19.7		1	2.0
830+33	831+60	127.4	22+50				
831+60	834+00	240.0	834+00	18.8		1	2.0
834+00	839+00	500.0	839+00	16.4		1	2.0
839+00	844+00	500.0	844+00	16.4		1	2.0
844+00	849+00	500.0	849+00	16.4		1	2.0
849+00	851+00	200.0	851+00	18.4		1	2.0
851+00	853+00	200.0	851+00			1	
853+00	858+00	500.0	853+00	17.4		1	2.0
858+00	863+00	500.0	863+00	16.4		1	2.0
863+00	868+00	500.0	868+00	17.4		1	2.0
868+00	873+00	500.0	868+00			1	
873+00	878+00	500.0	873+00	16.4		1	2.0
878+00	883+00	500.0	878+00	17.9		1	2.0
883+00	886+98	398.0	883+00	11.2		1	2.0
888+75	892+69	394.0	888+75	16.4		1	2.0
913+46	917+50	404.0	917+50	16.4		1	2.0
917+50	921+42	392.0	921+42	17.3		1	2.0
921+42	925+00	358.0	921+42			1	
925+00	928+57	357.0	925+00	18.6		1	2.0
928+57	931+72	315.0	931+72	17.6		1	2.0
931+72	936+00	428.0	931+72			1	
936+00	941+00	500.0	936+00	15.4		1	2.0
941+00	946+00	500.0	941+00	15.4		1	2.0
946+00	951+00	500.0	946+00	15.8		1	2.0
951+00	954+95	395.0	951+00	11.5		1	2.0
956+50	959+08	258.0	956+50	17.4		1	2.0
959+08	964+00	492.0	964+00	16.4		1	2.0
964+00	969+00	500.0	969+00	16.4		1	2.0
969+00	971+27	227.0	971+27	16.4		1	2.0
971+27	976+00	473.0	976+00			1	
976+00	981+00	500.0	976+00	16.4		1	2.0
981+00	985+47	447.0	981+00	16.4		1	2.0
985+47	989+00	353.0	989+00	18.3		1	2.0
989+00	992+68	368.0	992+68	13.0		1	2.0
992+68	997+79	511.0	992+68			1	
999+81	1004+00	419.0	999+81	16.4		1	2.0
1004+00	1007+91	391.0	1004+00	16.4		1	2.0
1007+91	1012+00	409.0	1012+00	16.4		1	2.0
1012+00	1016+00	400.0	1016+00	16.4		1	2.0
1016+00	1019+08	308.0	1019+08	16.4		1	2.0
1019+08	1021+64	256.0	1019+08			1	
1040+56	1043+50	294.0	1040+56	19.1		1	2.0
1043+50	1046+00	250.0	1046+00	17.2		1	2.0
1046+00	1051+00	500.0	1051+00	16.4		1	2.0
1051+00	1056+00	500.0	1056+00	16.4		1	2.0
1056+00	1061+00	500.0	1061+00	16.4		1	2.0
1061+00	1066+00	500.0	1066+00	16.4		1	2.0
1066+00	1071+00	500.0	1071+00	14.2		1	2.0
1071+00	1076+58	558.0	1076+58	11.2		1	2.0
1078+22	1082+00	378.0	1082+00	16.4		1	2.0
1082+00	1086+00	400.0	1086+00	16.4		1	2.0
1086+00	1088+93	293.0	1088+93	16.4		1	2.0
1119+93	1125+00	507.0	1125+00	16.4		1	2.0
1125+00	1130+00	500.0	1130+00	16.4		1	2.0
1130+00	1133+50	350.0	1133+50	16.4		1	2.0
SUBTOTALS		25578.1		932.6		63	112.0

NOTE: MINIMUM SLOPE IS 0.30%

PIPE UNDERDRAIN SCHEDULE
60107600 60108100 60100060 78001110

RAMP EDGE OF PAVEMENT (SEE PLANS FOR SIDE)							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL	PAINT PAVEMENT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCT NO	EACH	FOOT
RAMP A							
1+20	6+14	494.0	6+14	12.9		1	2.0
6+14	10+00	386.0	10+00	14.6		1	2.0
10+00	13+26	326.0	13+26	15.4		1	2.0
13+26	15+00	174.0	13+26			1	
15+00	17+26	226.0	15+00	17.8		1	2.0
17+26	19+00	174.0	19+00	16.9		1	2.0
19+00	21+50	250.0	21+50	17.0		1	2.0
21+50	24+00	250.0	24+00	17.0		1	2.0
24+00	26+16	215.6	781+86				
SUBTOTALS		2495.6		111.6		8	14.0
RAMP B							
0+00	2+00	200.0	789+00				
2+00	4+50	250.0	2+00	16.9		1	2.0
4+50	7+03	253.0	4+50	16.6		1	2.0
7+03	9+69	266.0	9+69	12.4		1	2.0
9+69	14+00	431.0	9+69			1	
14+00	18+68	468.0	14+00	14.6		1	2.0
SUBTOTALS		1868.0		60.5		5	8.0
RAMP C							
0+59	5+00	441.0	5+00	14.6		1	2.0
5+00	10+18	518.0	10+18	12.4		1	2.0
10+18	14+10	392.0	10+18			1	
14+10	17+50	340.0	14+10		7		
17+50	20+00	250.0	17+50	15.7		1	2.0
20+00	22+50	250.0	20+00	15.7		1	2.0
22+50	23+83	133.0	22+50	16.9		1	2.0
SUBTOTALS		2324.0		75.3		6	10.0
RAMP D							
0+00	1+50	150.0	1+50	15.4		1	2.0
1+50	4+00	250.0	4+00	15.5		1	2.0
4+00	6+37	237.0	6+37		7		
6+37	10+44	407.0	10+44	12.4		1	2.0
10+44	13+18	274.0	10+44			1	
13+18	19+04	586.0	13+18	12.9		1	2.0
SUBTOTALS		1904.0		56.2		5	8.0
NOTE: MINIMUM SLOPE IS 0.30%							
PROJECT TOTALS		117864		4105		300	536

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAP 310 (US 67/IL 104)
SHEET 26 OF 42
DRAWN BY EBB
CHECKED BY
DATE 10/10

3:57:19 PM Mar-25-2011 03:57:19PM \$FILE\$