

SIGNING SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	47
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS	SIGN PANEL			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY		CONCRETE FOUNDATION	
								TYPE 1	TYPE 2	TYPE 3				SIZE	POUND		CU YD
								SQ FT						FOOT	EACH		
FAP 310 (US 67)																	
849+97	WB	INSIDE	EAST	W2-2L SIGN #13 SIGN #14	36x36	SIDE ROAD SYMBOL 90 LT TO FRONTAGE ROAD CHAPIN'S BALL PARK	1	9.00			17.00						
852+97	WB	INSIDE	EAST	R3-1100L M6-2L	24x24 21x15	LEFT TURN LANE ARROW	1	4.00 2.19			17.00						
854+00	EB	OUTSIDE	WEST	SIGN #03	126x84	CONCORD ARENZVILLE 1/2 MILE	2		73.50				W10x22	968.00	2.36		
857+00	WB	INSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
857+00	WB	OUTSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
859+00	WB	INSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
859+00	WB	OUTSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
859+00		MEDIAN	NORTH	R1-2	36x36	YIELD	2	9.00			36.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
859+58	EB	OUTSIDE	SOUTH	R1-1	36x36	STOP	2	9.00			38.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
860+30	EB	OUTSIDE	NORTH	R1-1	36x36	STOP	2	9.00			38.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
860+70		MEDIAN	SOUTH	R1-2	36x36	YIELD	2	9.00			36.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
863+00	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
863+00	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
865+32	EB	INSIDE	WEST	R3-1100L M6-2L	24x24 21x15	LEFT TURN LANE ARROW	1	4.00 2.19			17.00						
866+64	EB	OUTSIDE	WEST	R3-1100R M6-2L	24x24 21x15	RIGHT TURN LANE ARROW	1	4.00 2.19			17.00						
869+64	EB	OUTSIDE	WEST	W2-2L SIGN #13	36x36	SIDE ROAD SYMBOL 90 LT TO FRONTAGE ROAD	1	9.00			17.00						
				SIGN #15		CHAPIN'S BALL PARK											
869+64	EB	INSIDE	WEST	W2-2L SIGN #13 SIGN #15	36x36	SIDE ROAD SYMBOL 90 LT TO FRONTAGE ROAD CHAPIN'S BALL PARK	1	9.00			17.00						
873+90	EB	MEDIAN	NORTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
877+22	WB	INSIDE	EAST	W2-1 SIGN #16	48x48 48x15	CROSS ROAD SYMBOL COOPER ST. CREWS LANE	2	5.00	16.00		36.00						
877+22	WB	OUTSIDE	EAST	W2-1 SIGN #16	48x48 48x15	CROSS ROAD SYMBOL COOPER ST. CREWS LANE	2	5.00	16.00		36.00						
880+00	EB	OUTSIDE	WEST	SIGN #01	126x84	CONCORD ARENZVILLE 1 MILE	2		73.50				W10x22	968.00	2.36		
880+22	WB	INSIDE	EAST	R3-1100L M6-2L	24x24 21x15	LEFT TURN LANE ARROW	1	4.00 2.19			17.00						
880+22	WB	OUTSIDE	EAST	R3-1100R M6-2L	24x24 21x15	RIGHT TURN LANE ARROW	1	4.00 2.19			17.00						
883+40	WB	INSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
883+40	WB	OUTSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
886+25	WB	INSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
886+25	WB	OUTSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
886+60		MEDIAN	SOUTH	R1-2	36x36	YIELD	2	9.00			36.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
887+00	EB	OUTSIDE	NORTH	R1-1	36x36	STOP	2	9.00			38.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
887+85	EB	OUTSIDE	SOUTH	R1-1	36x36	STOP	2	9.00			38.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
888+00		MEDIAN	NORTH	R1-2	36x36	YIELD	2	9.00			36.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
888+50	EB	OUTSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
888+50	EB	INSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
890+50	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
890+50	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 310 (US 67/IL 104)
 SHEET 31 OF 42
 DATE 10/10
 DRAWN BY EBB
 CHECKED BY

3:57:21 PM Mar-25-2011 03:57:21PM \$FILE\$