

SIGNING SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	49
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS	SIGN PANEL			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY		CONCRETE FOUNDATION
								TYPE 1	TYPE 2	TYPE 3				SIZE	POUND	
								SQ FT						FOOT	EACH	
FAP 310 (US 67)																
962+44	EB	INSIDE	WEST	R3-1100L	24x24	LEFT TURN LANE	1	4.00								
				M6-2L	21x15	ARROW		2.19								
965+44	EB	OUTSIDE	WEST	W2-1	36x36	CROSS ROAD SYMBOL	1	9.00				17.00				
				SIGN #18	36x09	BETHAL LANE		2.25								
965+44	EB	INSIDE	WEST	W2-1	36x36	CROSS ROAD SYMBOL	1	9.00				17.00				
				SIGN #18	36x09	BETHAL LANE		2.25								
970+23	WB	INSIDE	EAST	R3-1100L	24x24	LEFT TURN LANE	1	4.00				17.00				
				M6-2L	21x15	ARROW		2.19								
972+50	WB	INSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
972+50	WB	OUTSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
974+50	WB	INSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
974+50	WB	OUTSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
974+92		MEDIAN		R1-2	36x36	YIELD	2	9.00				36.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
975+25	EB	OUTSIDE		R1-1	36x36	STOP	2	9.00				38.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-3A	24x18	DIVIDED HIGHWAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
975+65	WB	OUTSIDE		R1-1	36x36	STOP	2	9.00				38.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-3A	24x18	DIVIDED HIGHWAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
976+15		MEDIAN		R1-2	36x36	YIELD	2	9.00				36.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
976+50	EB	OUTSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
976+50	EB	INSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
978+50	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
978+50	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
980+75	EB	INSIDE	WEST	R3-1100L	24x24	LEFT TURN LANE	1	4.00				17.00				
				M6-2L	21x15	ARROW		2.19								
988+56	WB	INSIDE	EAST	W2-2R	36x36	SIDE ROAD SYMBOL 90 RT	1	9.00				17.00				
				SIGN #19	36x15	ST. PAULS CHURCH RD		3.75								
988+56	WB	OUTSIDE	EAST	W2-2R	36x36	SIDE ROAD SYMBOL 90 RT	1	9.00				17.00				
				SIGN #19	36x15	ST. PAULS CHURCH RD		3.75								
991+56	WB	OUTSIDE	EAST	R3-1100R	24x24	RIGHT TURN LANE	1	4.00				17.00				
				M6-2L	21x15	ARROW		2.19								
992+76	WB	INSIDE	EAST	R3-1100L	24x24	LEFT TURN LANE	1	4.00				17.00				
				M6-2L	21x15	ARROW		2.19								
995+00	WB	INSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
995+00	WB	OUTSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
997+50	WB	INSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
997+50	WB	OUTSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
997+75		MEDIAN		R1-2	36x36	YIELD	2	9.00				36.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
998+20	EB	OUTSIDE		R1-1	36x36	STOP	2	9.00				38.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-3A	24x18	DIVIDED HIGHWAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
998+70	WB	OUTSIDE		R1-1	36x36	STOP	2	9.00				38.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-3A	24x18	DIVIDED HIGHWAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
999+15		MEDIAN		R1-2	36x36	YIELD	2	9.00				36.00				
				R6-1R	36x12	ONE WAY		3.00								
				R6-1L	36x12	ONE WAY		3.00								
999+50	EB	OUTSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
999+50	EB	INSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00				17.00				
1001+50	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
1001+50	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00				16.00				
1005+45	EB	INSIDE	WEST	R3-1100L	24x24	LEFT TURN LANE	1	4.00				17.00				
				M6-2L	21x15	ARROW		2.19								
1007+45	EB	INSIDE	SOUTH	R6-1R	36x12	ONE WAY	1	3.00				15.00				
1008+45	EB	OUTSIDE	WEST	W2-2L	36x36	SIDE ROAD SYMBOL 90 LT	1	9.00				17.00				
				SIGN #19	36x15	ST. PAULS CHURCH RD		3.75								

3:57:22 PM

Mar-25-2011 03:57:22PM

\$FILE\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 310 (US 67/IL 104)
 SHEET 33 OF 42
 DRAWN BY EBB
 CHECKED BY
 DATE 10/10