

SIGNING SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	52
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS	SIGN PANEL			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY		CONCRETE FOUNDATION	
								TYPE 1	TYPE 2	TYPE 3				SIZE	POUND		CU YD
								SQ FT						FOOT	EACH		
FAP 310 (US 67)																	
1100+90		MEDIAN	NORTH	R1-2	36x36	YIELD	2	9.00									
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
1101+25	EB	OUTSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1101+25	EB	INSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1103+25	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1103+25	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1105+10	EB	INSIDE	SOUTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
1106+00	WB	INSIDE	EAST	W9-1L	36x36	LEFT LANE ENDS AHEAD WITH FLAG	1	9.00			17.00						
1106+00	WB	OUTSIDE	EAST	W9-1L	36x36	LEFT LANE ENDS AHEAD WITH FLAG	1	9.00			17.00						
1105+69	EB	INSIDE	WEST	R3-1100L	24x24	LEFT TURN LANE	1	4.00			17.00						
				M6-2L	21x15	ARROW		2.19									
1106+90	EB	OUTSIDE	WEST	R3-1100R	24x24	RIGHT TURN LANE	1	4.00			17.00						
				M6-2L	21x15	ARROW		2.19									
1109+00	WB	INSIDE	EAST	W4-2L	36x36	MERGE RIGHT AHEAD WITH FLAG	1	9.00			17.00						
1109+00	WB	OUTSIDE	EAST	W4-2L	36x36	MERGE RIGHT AHEAD WITH FLAG	1	9.00			17.00						
1109+90	EB	OUTSIDE	WEST	W2-2R	36x36	SIDE ROAD SYMBOL 90 RT	2	9.00			34.00						
				SIGN #22	57x09	HART'S GRAVEL RD		3.56									
1109+90	EB	INSIDE	WEST	W2-2R	36x36	SIDE ROAD SYMBOL 90 RT	2	9.00			34.00						
				SIGN #22	57x09	HART'S GRAVEL RD		3.56									
1111+25	EB	INSIDE	SOUTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
1115+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1116+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1117+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1118+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1119+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1119+00	EB	INSIDE	SOUTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
1119+70	WB	INSIDE	NORTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
1120+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1121+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1122+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1123+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1123+25	WB	INSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1123+25	WB	OUTSIDE	WEST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1124+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1125+00	WB	INSIDE	EAST	W1-8	18x24	CHEVRON	1	3.00			14.00						
1125+25	WB	INSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1125+25	WB	OUTSIDE	WEST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1125+60		MEDIAN	SOUTH	R1-2	36x36	YIELD	2	9.00			36.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
1125+90	EB	OUTSIDE	SOUTH	R1-1	36x36	STOP	2	9.00			38.00						
			SOUTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			NORTH	R6-1L	36x12	ONE WAY		3.00									
1126+50	WB	OUTSIDE	NORTH	R1-1	36x36	STOP	2	9.00			38.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			NORTH	R6-3A	24x18	DIVIDED HIGHWAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
1126+80		MEDIAN	NORTH	R1-2	36x36	YIELD	2	9.00			36.00						
			NORTH	R6-1R	36x12	ONE WAY		3.00									
			SOUTH	R6-1L	36x12	ONE WAY		3.00									
1127+25	EB	OUTSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1127+25	EB	INSIDE	EAST	R5-1	36x36	DO NOT ENTER	1	9.00			17.00						
1129+25	EB	OUTSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1129+25	EB	INSIDE	EAST	R5-1A	36x24	WRONG WAY	1	6.00			16.00						
1130+00	WB	OUTSIDE	EAST	W1-4R	36x36	REVERSE CURVE RIGHT AHEAD	1	9.00			17.00						
1133+55	EB	INSIDE	SOUTH	R6-1R	36x12	ONE WAY	1	3.00			15.00						
1139+60		MEDIAN	EAST	W6-3	36x36	TWO-WAY TRAFFIC AHEAD	2	9.00			17.00						
			WEST	R4-7	48x60	KEEP RIGHT			20.00								
1048+00		OUTSIDE	WEST	W6-1	36x36	DIVIDED HIGHWAY AHEAD	1	9.00			17.00						
1151+00		OUTSIDE	WEST	W1-4R	36x36	REVERSE CURVE RIGHT AHEAD	1	9.00			17.00						
SUB TOTALS - US 67								2263.36	304.00	865.00	5719.00	440.00	2	6505.00	15.04		

3:57:23 PM

Mar-25-2011 03:57:23PM

\$FILE\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 310 (US 67/IL 104)
 SHEET 36 OF 42
 DATE 10/10
 DRAWN BY EBB
 CHECKED BY