

SIGNING SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	55
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS	SIGN PANEL			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY		CONCRETE FOUNDATION	
								TYPE 1	TYPE 2	TYPE 3				SIZE	POUND		CU YD
38+75	RELOCATED CREWS LN	OUTSIDE	WEST	R11-I100	36x36	ROAD ENDS	1	9.00				17.00					
				SIGN #		PRIVATE DRIVE											
39+58.10	RELOCATED CREWS LN	OUTSIDE	EAST	R1-1	36x36	STOP	1	9.00				18.00					
40+53.04	RELOCATED CREWS LN	OUTSIDE	WEST	R1-1	36x36	STOP	1	9.00				18.00					
				R1-I100	30x18	CROSS TRAFFIC DOES NOT STOP		3.75									
46+00.00	RELOCATED CREWS LN	OUTSIDE	EAST	W1-1R	36x36	TURN RIGHT SIGN	1	9.00				17.00					
				W13-1	24x24	25 MPH		4.00									
46+00	RELOCATED CREWS LN	OUTSIDE	WEST	W3-1a	36x36	STOP AHEAD	1	9.00				17.00					
60+00.00	RELOCATED CREWS LN	OUTSIDE	NORTH	W1-1L	36x36	TURN LEFT SIGN	1	9.00				17.00					
				W13-1	24x24	25 MPH		4.00									
52+00	RELOCATED CREWS LN	OUTSIDE	EAST	W1-8L	18x24	CHEVRON	1	3.00				14.00					
			WEST	W1-8R	18x24	CHEVRON		3.00									
52+80	RELOCATED CREWS LN	OUTSIDE	EAST	W1-8L	18x24	CHEVRON	1	3.00				14.00					
			WEST	W1-8R	18x24	CHEVRON		3.00									
53+60	RELOCATED CREWS LN	OUTSIDE	EAST	W1-8L	18x24	CHEVRON	1	3.00				14.00					
			WEST	W1-8R	18x24	CHEVRON		3.00									
54+40	RELOCATED CREWS LN	OUTSIDE	EAST	W1-8L	18x24	CHEVRON	1	3.00				14.00					
			WEST	W1-8R	18x24	CHEVRON		3.00									
55+20	RELOCATED CREWS LN	OUTSIDE	EAST	W1-8L	18x24	CHEVRON	1	3.00				14.00					
			WEST	W1-8R	18x24	CHEVRON		3.00									
573+75	EX US 67/ IL 104		WEST	R11-I100	36x36	ROAD ENDS	1	9.00				17.00					
				OM4-1	18x18	OBJECT MARKER	1	2.25				16.00					
				OM4-1	18x18	OBJECT MARKER	1	2.25				16.00					
568+75	EX US 67/ IL 104	OUTSIDE	WEST	W8-I108	36x36	ROAD ENDS 500 FT	1	9.00				17.00					
565+25	EX US 67/ IL 104	OUTSIDE	WEST	W14-1	30x30	DEAD END	1	6.25				17.00					
565+25	EX US 67/ IL 104	OUTSIDE	EAST	R1-1	30x30	STOP	1	6.25				17.00					
564+70	EX US 67/ IL 104	OUTSIDE	SOUTH	R1-1	30x30	STOP	1	6.25				17.00					
563+50	EX US 67/ IL 104	OUTSIDE	WEST	R1-1	30x30	STOP	1	6.25				17.00					
558+50	EX US 67/ IL 104	OUTSIDE	WEST	W3-1a	36x36	STOP AHEAD SYMBOL	1	9.00				17.00					
540+00	EX US 67/ IL 104	OUTSIDE	EAST	W1-4R	36x36	REVERSE CURVE RIGHT AHEAD	1	9.00				17.00					
69+00	BETHEL LANE	OUTSIDE	SOUTH	W2-1	36x36	CROSS ROAD AHEAD	1	9.00				17.00					
71+00	BETHEL LANE	OUTSIDE	SOUTH	W1-2R	36x36	CURVE RIGHT AHEAD	1	9.00				17.00					
				W13-1	24x24	35 MPH		4.00									
74+50	BETHEL LANE	OUTSIDE	SOUTH	W3-1a	36x36	STOP AHEAD	1	9.00				17.00					
76+50	BETHEL LANE	OUTSIDE	SOUTH	SIGN #		JACKSONVILLE/BEARDSTOWN	2										
77+00	BETHEL LANE	OUTSIDE	NORTH	W2-1	36x36	CROSS ROAD AHEAD	1	9.00				17.00					
78+00	BETHEL LANE	OUTSIDE	NORTH	W1-2L	36x36	CURVE LEFT AHEAD	1	9.00				17.00					
				W13-1	24x24	35 MPH		4.00									
81+50	BETHEL LANE	OUTSIDE	SOUTH	W1-4L	36x36	REVERSE CURVE LEFT AHEAD	1	9.00				17.00					
				W13-1	24x24	25 MPH		4.00									
87+50	BETHEL LANE	OUTSIDE	NORTH	W3-1a	36x36	STOP AHEAD	1	9.00				17.00					
90+00	BETHEL LANE	OUTSIDE	NORTH	W2-2R	36x36	SIDE ROAD SYMBOL 90 RT	1	9.00				17.00					
95+00	BETHEL LANE	OUTSIDE	NORTH	W1-4L	36x36	REVERSE CURVE LEFT AHEAD	1	9.00				17.00					
				W13-1	24x24	25 MPH		4.00									
591+42	SERVICE RD 91	OUTSIDE	SOUTH	R1-1	36x36	STOP	1	9.00				17.00					
591+52	SERVICE RD 91	OUTSIDE	NORTH	W14-1	36x36	DEAD END	1	9.00				17.00					
593+90	SERVICE RD 91		NORTH	R11-I100	36x36	ROAD ENDS	1	9.00				17.00					
				OM4-1	18x18	OBJECT MARKER	1	2.25				16.00					
				OM4-1	18x18	OBJECT MARKER	1	2.25				16.00					

3:57:24 PM

Mar-25-2011 03:57:24PM

\$FILE\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 310 (US 67/IL 104)  
 SHEET 39 OF 42  
 DATE 10/10  
 DRAWN BY EBB  
 CHECKED BY