

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	57
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

REMOVE SIGN COMPLETE

X7240205

STATION	LANE	SIDE	FACING	SIGN NUMBER (MUTCD)	SIZE (IN)	MESSAGE	NUMBER OF POSTS	REMOVE SIGN COMPLETE EACH
765+00 TO 770+00				W1-B	18x24	CHEVRON		1
776+80 TO 781+80				W1-B	18x24	CHEVRON		1
783+00 TO 791+00				W1-B	18x24	CHEVRON		1
744+25	WB	OUTSIDE	EAST	R2-5c	48x60	SPEED ZONE AHEAD WITH FLAG	1	1
				R1-1101	30x30	55 MPH		1
744+25	WB	MEDIAN	EAST	R2-5c	48x60	SPEED ZONE AHEAD WITH FLAG	1	1
				R1-1101	30x30	55 MPH		1
748+97	WB	MEDIAN	EAST	R2-1	48x60	SPEED LIMIT 55 WITH FLAG	2	1
748+97	WB	OUTSIDE	EAST	R2-1	48x60	SPEED LIMIT 55 WITH FLAG	2	1
754+72	WB	MEDIAN	EAST	W9-1L	36x36	LEFT LANE ENDS WITH FLAG	1	1
754+72	WB	OUTSIDE	EAST	W9-1L	36x36	LEFT LANE ENDS WITH FLAG	1	1
756+81	WB	MEDIAN	WEST	W8-1103	36x36	EXPRESSWAY ENDS 1000 FT		1
756+81	WB	OUTSIDE	WEST	W8-1103	36x36	EXPRESSWAY ENDS 1000 FT		1
758+81	WB	MEDIAN	WEST	W9-2R	36x36	LANE ENDS MERGE RIGHT	1	1
758+81	WB	OUTSIDE	WEST	W9-2R	36x36	LANE ENDS MERGE RIGHT	1	1
113+75	OLD 67	OUTSIDE	EAST	W14-1	30x30	DEAD END	1	1
761+81	WB	MEDIAN	SOUTH	W1-42	36x36	REVERSE CURVE LT WITH FLAG	1	1
761+81	WB	OUTSIDE	SOUTH	W1-42	36x36	REVERSE CURVE LT WITH FLAG	1	1
774+25	WB	OUTSIDE	EAST	W6-3	36x36	TWO-WAY TRAFFIC	1	1
774+25	WB	MEDIAN	EAST	W6-3	36x36	TWO-WAY TRAFFIC	1	1
774+25	WB	MEDIAN	WEST	R4-7	36x48	KEEP RIGHT		1
779+90	WB	MEDIAN	EAST	W1-42	36x36	REVERSE CURVE LT	1	1
782+00	EB	OUTSIDE	WEST	W6-1	36x36	DIVIDED HIGHWAY SYMBOL	1	1
89+30	OLD 67	OUTSIDE	EAST	W8-1108	36x36	ROAD ENDS 500 FT	1	1
84+25	OLD 67	CL	WEST	R11-1100	36x36	ROAD ENDS WITH OBJECT MARKERS	3	1
34+30	CONNECTOR	OUTSIDE	EAST	W2-2R	48x48	SIDE ROAD SYMBOL 90 RT	1	1
21+00 TO 30+00	CONNECTOR			W16-8	36x15	ARENZVILLE RD		
35+50 TO 41+50	CONNECTOR			W1-B	18x24	CHEVRON		1
37+00	CONNECTOR	OUTSIDE	EAST	W1-B	18x24	CHEVRON		1
				R3-1100R	24x24	RIGHT TURN LANE	1	1
64+50	CONNECTOR	OUTSIDE	WEST	M6-2R	21x15	ARROW		
805+80	EB	OUTSIDE	SOUTH	W1-4L	36x36	REVERSE CURVE LT SYMBOL	1	1
				R1-1	36x36	STOP	1	1
TOTAL								30

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL  
78300200

STATION TO STATION	SIDE	SPACING	EACH
EX US 67 / IL 104			
81+30.0 97+85.0	CL	80	21
48+50.0 52+50.0	CL	80	5
0+00.0 3+00.0	CL	80	4
578+95.0 589+54.3	CL	80	14
556+00.0 575+75.0	CL	80	25
521+80.0 524+68.0	CL	80	4
481+35.0 484+80.0	CL	80	5
351+20.0 353+65.0	CL	80	4
312+20.0 315+60.0	CL	80	5
EX CONCORD ROAD			
25+30.0 29+55.0	CL	80	6
TOTAL			93
USE			100

NOTE: THIS IS AN ESTIMATED QUANTITY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES  
FAP 310 (US 67/IL 104)  
SHEET 41 OF 42

DATE 10/10  
DRAWN BY EBB  
CHECKED BY

3:57:25 PM

Mar-25-2011 03:57:25PM

\$FILE\$