

STAGE CONSTRUCTION PAVMENT MARKING SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	125
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STAGE	ROADWAY	STATION TO STATION	SIDE	78001120				78001180	REMOVAL REQUIRED	78300100	
				PAINT PAVEMENT MARKING - LINE 5"				LINE 24"		PAVEMENT MARKING REMOVAL	
				WHITE		YELLOW		WHITE			
SOLID	SKIP-DASH	SOLID	SKIP-DASH	SOLID				SO FT			
FT	FT	FT	FT	FT							
2	US 67 FRONTAGE RD	6+99 51+15	RT						NO - HMA OVERLAY		
			CL			8832			NO - HMA OVERLAY		
		LT	4416						NO - HMA OVERLAY		
			51+55	RT						NO - HMA OVERLAY	
			53+05	LT				12		NO - HMA OVERLAY	
	TEMPORARY ACCESS RD	0+00 30+27	RT	3114				12	YES - ACROSS FAP 310	38	
			CL			5968			YES - ACROSS FAP 310	76	
			LT	3047					YES - ACROSS FAP 310	39	
			29+84	RT					NO - PVMT REMOVAL		
	TR 115 (REL CYLINDER HEAD RD)		99+43	RT				12	YES	22	
3	FAP 310 (US 67) - EB	932+80 937+12	RT			432		11	YES	180	
			CL		90				YES	38	
	FAP 310 (US 67) - WB	921+97 933+00	RT	1103						YES	460
			CL		340					YES	142
		928+24 935+40	LT			716				YES	299
			LT - CL			660				YES	275
		942+00 945+67	CL			367				YES	153
			CL			1000				YES	417
		945+67 970+26	LT	2459						YES	1025
			CL				430			YES	180
		967+76 970+26	CL			500				YES	209
			CL				500			YES	209
	1110+82 1131+00	LT	2268						YES	945	
		CL			500				YES	209	
	CROSSOVER A	18+60 27+19	LT	859						YES - ACROSS FAP 310	111
			RT			859				YES - ACROSS FAP 310	106
	TRANSITION A	0+00 9+89	LT	989						NO - PVMT REMOVAL	
			CL			1978				NO - PVMT REMOVAL	
			RT	989						NO - PVMT REMOVAL	
	TRANSITION B	0+00 6+30	LT	630						NO - PVMT REMOVAL	
CL					1260				NO - PVMT REMOVAL		
RT			630						NO - PVMT REMOVAL		
TRANSITION C	49+50 61+75	LT	1225						NO - PVMT REMOVAL		
		CL			2450				NO - PVMT REMOVAL		
		RT	1225						NO - PVMT REMOVAL		
EX US 67	309+70 312+20	CL			500				NO		
		CL			500				NO - PVMT REMOVAL		
		CL			500				NO - PVMT REMOVAL		
4	FAP 310 (US 67) - EB	933+50 937+12	CL			362			YES	151	
			CL			1006			YES	420	
		937+12 1126+84	RT	18972						YES	7905
			CL				4550			YES	1896
		1124+34 1126+84	CL			500				YES	209
	FAP 310 (US 67) - WB	921+97 928+57	RT - CL	660					YES	275	
	CROSSOVER A	10+00 18+60	LT			860				YES - ACROSS FAP 310	120
			RT	860						YES - ACROSS FAP 310	108
	TRANSITION D	0+00 17+25	CL			3450				YES	1438
			RT	1725						YES	719
<b>SUB-TOTALS:</b>				<b>49,587</b>	<b>430</b>	<b>33,200</b>	<b>5,480</b>	<b>47</b>		<b>18,374</b>	
<b>TOTALS:</b>				<b>88,697</b>				<b>47</b>		<b>18,374</b>	

NOTE: SEE STRIPING PLANS AND SCHEDULES FOR FINAL STRIPING.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**TRAFFIC CONTROL AND STAGING  
 DETAILS**  
 FAP 310 (US 67/IL 104)  
 SHEET 27 OF 27

DRAWN BY SEB  
 CHECKED BY  
 DATE 8/09

1:12:10 PM Mar-29-2011 01:12:10PM \$FILE\$