



ROAD ENDS
PRIVATE DRIVE

STA 38+75.00
CENTERLINE
R11-1100 (3636)
"ROAD ENDS"
SIGN #
"PRIVATE DRIVE"
(SEE DETAILS)

STOP

STA 39+58.10
RT, 12' OFF EOP
STA 40+53.04
LT, 12' OFF EOP
R1-1 (3636)
"STOP"
R1-1100 (3018)
"CROSS TRAFFIC
DOES NOT STOP"

STA 46+00.00
LT, 20' OFF EOP
W3-1a (3636)
"STOP AHEAD"

25
MPH

STA 46+00.00
RT, 20' OFF EOP
W1-1R (3636)
W13-1 (2424)
"CURVE RIGHT AHEAD"
"25 MPH"

PAVEMENT MARKING LEGEND

- (A) PR RAISED REFLECTIVE PAVEMENT MARKERS, ONE-WAY CRYSTAL
- (B) PR RAISED REFLECTIVE PAVEMENT MARKERS, ONE-WAY AMBER
- (C) PR RAISED REFLECTIVE PAVEMENT MARKERS, TWO-WAY AMBER
- (1) PR URETHANE PAVEMENT MARKING- LINE 5" (WHITE SKIP DASH)
- (2) PR URETHANE PAVEMENT MARKING- LINE 5" (YELLOW SKIP DASH)
- (3) PR URETHANE PAVEMENT MARKING- LINE 5" (SOLID WHITE)
- (4) PR URETHANE PAVEMENT MARKING- LINE 5" (SOLID YELLOW)
- (5) PR URETHANE PAVEMENT MARKING- LINE 6" (SOLID WHITE)
- (6) PR URETHANE PAVEMENT MARKING- LINE 8" (SOLID WHITE)
- (7) PR URETHANE PAVEMENT MARKING- LINE 12" (SOLID WHITE)
- (8) PR URETHANE PAVEMENT MARKING- LINE 12" (SOLID YELLOW)
- (9) PR PREFORMED PLASTIC PAVEMENT MARKING- LINE 24" (SOLID WHITE)
- (10) PR PREFORMED PLASTIC PAVEMENT MARKING- LETTERS & SYMBOLS (LARGE ARROWS= 15.6 SF/EACH)

TYPICAL SIDE STREET STOP SIGN INSTALLATION

R6-1L (3612) "ONE WAY LT"
BACK TO BACK
R61R (3612) "ONE WAY RT"
R1-1 (3636) "STOP"
R6-3A (2418) "DIVIDED HIGHWAY"
INSTALL ON 2 TELESCOPING STEEL POST

TYPICAL SIDE STREET YIELD SIGN INSTALLATION

R6-1L (3612) "ONE WAY LT"
BACK TO BACK
R61R (3612) "ONE WAY RT"
R1-2 (3636) "YIELD"
INSTALL ON 2 TELESCOPING STEEL POST

FILE NAME =	USER NAME = Sparksgw	DESIGNED -	REVISED -
c:\pwork\work\pwork\sparksgw\0264881\P&P	Sideroads1-14.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1".	CHECKED -	REVISED -
	PLOT DATE = Mar-30-2011 08:49:49AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

STRIPING & SIGNING PLAN SHEETS
RELOCATED CREWS LANE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3	Morgan	793	285
CONTRACT NO. 72667			ILLINOIS FED. AID PROJECT	