CONTRACT NO. 72667

| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 310 | 69-3 | MORGAN | 793 | 717 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

FINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TYPICAL SHEET — AREAS — AREAS CHECKED — BY — DATE

ORIGINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TYPICAL SHEET — AREAS — AREAS CHECKED — BY — DATE

10:54:01 AM

Mar-30-2011 10:54:01AM

$FILE$

160 150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120

625 620 615 610

90.00'

℄ TEMP ACCESS RD STA 17+51.82

SEE TEMPORARY ACCESS ROAD CROSS SECTIONS FOR STAGE I CONSTRUCTION

AC PR ROW TCE

STAGE 2 ⟵ ⟶ STAGE 3

621.38 -3.72% 4.28 % 620.69 -4.28%

1:6 1:3 1:3 1:6 1:3 1:3

S.D. 614.70 S.D. 614.51

STAGE 2 CUT=6.1 SQ FT FILL=229.7 SQ FT T.S.=15.2 SQ FT
STAGE 3 CUT=70.6 SQ FT FILL=24.9 SQ FT T.S.=27.9 SQ FT

8+00

90.00'

℄ TEMP ACCESS RD STA 16+51.82

SEE TEMPORARY ACCESS ROAD CROSS SECTIONS FOR STAGE I CONSTRUCTION

AC PR ROW TCE

STAGE 2 ⟵ ⟶ STAGE 3

622.36 -4.00% 1.50 % 622.12 -4.00%

1:6 1:3 1:3 1:6 1:3 1:3

S.D. 614.19 S.D. 614.35

STAGE 2 CUT=13.0 SQ FT FILL=311.9 SQ FT T.S.=18.9 SQ FT
STAGE 3 CUT=58.7 SQ FT FILL=21.5 SQ FT T.S.=26.7 SQ FT

7+00

90.00'

℄ TEMP ACCESS RD STA 15+51.82

SEE TEMPORARY ACCESS ROAD CROSS SECTIONS FOR STAGE I CONSTRUCTION

AC PR ROW TCE

STAGE 2 ⟵ ⟶ STAGE 3

624.04 -4.00% 1.50 % 623.80 -4.00%

1:6 1:3 1:3 1:6 1:3 1:3

S.D. 613.68 S.D. 614.05

STAGE 2 CUT=20.5 SQ FT FILL=448.3 SQ FT T.S.=23.0 SQ FT
STAGE 3 CUT=52.3 SQ FT FILL=25.9 SQ FT T.S.=27.9 SQ FT

6+00

90.00'

℄ TEMP ACCESS RD STA 14+51.82

SEE TEMPORARY ACCESS ROAD CROSS SECTIONS FOR STAGE I CONSTRUCTION

AC PR ROW TCE

STAGE 2 ⟵ ⟶ STAGE 3

625.72 -4.00% 1.50 % 625.48 -4.00%

1:6 1:3 1:3 1:6 1:3 1:3

S.D. 613.18 S.D. 613.75

STAGE 2 CUT=32.9 SQ FT FILL=597.8 SQ FT T.S.=27.4 SQ FT
STAGE 3 CUT=51.6 SQ FT FILL=21.0 SQ FT T.S.=25.7 SQ FT

5+00

RAMP C STA 5+00 TO STA 8+00