

GENERAL NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCE NOTICE IS REQUIRED. ANY DAMAGE TO THE UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE, INCLUDING TEMPORARY REPAIRS WHICH MAY BE REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS.
- THE LOCATIONS OF THOSE BURIED AND ABOVEGROUND UTILITIES SHOWN ARE APPROXIMATE, ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTIONS PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVEGROUND UTILITY LOCATION, IDENTIFICATION, AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REROUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVEGROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- THE THICKNESS OF HOT-MIX ASPHALT SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
- FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SANDBAGS PER BARRICADE.
- THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

GRANULAR MATERIALS	2.05	TONS/CU YD
HOT-MIX ASPALT MATERIAL (PRIME COAT)	0.00038	TON/SO YD
HOT-MIX ASPHALT SURFACE CSE	112	LBS/SO YD/IN
HOT-MIX ASPHALT BINDER CSE	112	LBS/SO YD/IN
AGGREGATE (PRIME COAT)	0.002	TON/SO YD
- ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- UNLESS NOTED OTHERWISE, STATIONS AND OFFSETS REFER TO CENTERLINE OF PROJECT.
- IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- ANY REFERENCES OR CALL-OUTS IN THESE PLANS TO "BITUMINOUS CONCRETE" SHALL BE INTERPRETED TO MEAN "HOT-MIX ASPHALT".

COMMITMENTS

NONE

The following mixture requirements are applicable for this project:

Mixture Use(s)	Polymerized Hot-Mix Asphalt Surface Course, Mix "E", N105	Polymerized Hot-Mix Asphalt Binder Course, IL-19.0, N105				
AC/PG:	SBS PG 76-22	SBS PG 76-22				
Design Air Voids:	4.0% @ N DESIGN =105	4.0% @ N DESIGN =105				
Mixture Composition: (Gradation Mixture)	IL 9.5 OR 12.5	IL 19.0				
Friction Aggregate:	MIX "E"	N/A				

DISTRICT SIX	
EXAMINED <u>Feb 7</u> 20 <u>11</u>	<i>Oil Well</i>
OPERATIONS ENGINEER	
EXAMINED <u>JANUARY 28</u> 20 <u>11</u>	<i>Tommy Ford</i>
PROJECT IMPLEMENTATION ENGINEER	
EXAMINED <u>FEBRUARY 1, 20 11</u>	<i>John C. W. [Signature]</i>
PROGRAM DEVELOPMENT ENGINEER	

FILE NAME =	USER NAME = pererava	DESIGNED -	REVISED -
c:\pwwork\pwwork\pererava\d0255556\0672E08-sht-gennote.dgn	2E08-sht-gennote.dgn	DRAWN -	REVISED -
PLOT SCALE = 100.0000 "/ IN.	CHECKED -	REVISED -	REVISED -
PLOT DATE = Feb-03-2011 11:13:17AM	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL NOTES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.I. RTE. 55	SECTION (84-3-2) I-3	COUNTY SANGAMON	TOTAL SHEETS 12	SHEET NO. 2
CONTRACT NO. 72E08							
ILLINOIS FED. AID PROJECT							