

TEMPORARY RAMPS					
LOCATION STATION	TO STATION	DESCRIPTION	WIDTH (FT)	AREA (SQ YD)	
FAP 714 (IL 48)					
STA. 41+80.00	TO STA. 42+15.00	BUTT-JOINT	24.0	13.4	
STA. 191+50.00	TO STA. 191+85.00	BUTT-JOINT	28.0	15.6	
SIDE ROADS					
STA. 64+63.50 LT.		OAK AVE.	60.0	33.3	
STA. 82+85.63 RT.		CR 2300 N	80.0	44.4	
STA. 155+25.25 LT.		24 TH. AVE.	80.0	44.4	
STA. 155+34.00 RT.		24 TH. AVE.	80.0	44.4	
STA. 171+63.03 LT.		HOLMER ST.	80.0	44.4	
STA. 178+59.06 LT.		OAK ST.	50.0	27.9	
STA. 182+15.58 LT.		FARLEY ST.	75	41.8	
STA. 185+82.10 LT.		CEDER ST.	55	30.6	
STA. 189+39.60 RT.		MAIN ST.	80	44.4	
STA. 189+49.91 LT.		MAIN ST.	80	44.4	
				TOTAL	429.0

HOT-MIX ASPHALT SHOULDER SCHEDULE									
LOCATION STATION	TO STATION	LENGTH (FT)	WIDTH (FT)	PAVED SHOULDER REMOVAL (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 6 1/2" (SQ YD)	HMA SURFACE COURSE MIX "C" N70 (1 1/2") (TON)	BIT. MAT. PRIME CT. (TON)	EXCAVATING & GRADING EXIST SHOULDERS (UNIT)	
FAP 714 (IL 48)									
STA. 186+14.00 LT.	TO STA. 191+50.00 LT.	536.00	4.00	119.2	195.0	16.4	0.1	4.5	
STA. 185+57.00 RT.	TO STA. 191+50.00 RT.	593.00	4.00	131.8	233.0	19.6	0.1	5.5	
				TOTALS	251.0	428.0	36.0	0.2	10.0

SHORT-TERM PAVEMENT MARKING					
LOCATION STATION TO STATION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK (FT)	WORK ZONE PAVE MARK REM (SQ FT)
IL (48)					
STA. 41+80.00 TO STA. 191+85.00	15005.0	4/40'	3	4514.0	497
				TOTAL	4514.0

AGGREGATE SHOULDERS TYPE B					
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	(TONS)		
IL (48)					
LEFT					
STA. 41+80.00 TO STA. 42+15.00	35.00	3'	2.0		
STA. 42+15.00 TO STA. 186+14.00	14399.00	3'	820.0		
STA. 186+14.00 TO STA. 191+50.00	536.00	3'	30.5		
STA. 191+50.00 TO STA. 191+85.00	35.00	3'	2.0		
RIGHT					
STA. 41+80.00 TO STA. 42+15.00	35.00	3'	2.0		
STA. 42+15.00 TO STA. 185+57.00	14342.00	3'	816.7		
STA. 185+57.00 TO STA. 191+50.00	593.00	3'	33.8		
STA. 191+50.00 TO STA. 191+85.00	35.00	3'	2.0		
				TOTAL	1709.0

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE				
LOCATION STATION TO STATION	LENGTH (FT)	TWO-WAY AMBER (EACH)	REMOVAL (EACH)	
IL (48)				
STA. 42+15.00 TO STA. 191+50.00	14935.0	188	188	
		TOTAL	188	188

PAVEMENT MARKING			
LOCATION STATION TO STATION	LENGTH (FT)	PAINT PAVEMENT MARKING - LINE 5"	
		(FT)	(FT)
IL (48)			
		EDGE LINE	SKIP-DASH
		WHITE	YELLOW
STA. 41+80.00 TO STA. 191+85.00	15005.0		3761
RIGHT			
STA. 41+80.00 TO STA. 191+85.00	15005.0	14818.0	
LEFT			
STA. 41+80.00 TO STA. 191+85.00	15005.0	14473.0	
		SUB-TOTAL	3,761.0
		TOTAL	33,052.0

NOTE: QUANTITY FOR TEMPORARY PAVEMENT MARKING-LINE 5"
SAME AS PAINT PAVEMENT MARKING-LINE 5"

REVISED 3/28/2011

FILE NAME =	USER NAME = perereve	DESIGNED -	REVISED - 3/28/2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pudat\perereve\08255647\062829-ahh-schedule.dgn	DRAWN -	REVISED -	714					137RS-6	MONTGOMERY	16	6	
PLOT SCALE = 48.0000' / IN.	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.					CONTRACT NO. 72E29				
PLOT DATE = Mar-28-2011 08:58:42AM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									