

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0014
CODE NO	ITEM	UNIT		
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	122	122
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	1071	1071
42001200	PAVEMENT FABRIC	SQ YD	1071	1071
44004250	PAVED SHOULDER REMOVAL	SQ YD	972	972
50102400	CONCRETE REMOVAL	CU YD	5.6	5.6
50157300	PROTECTIVE SHIELD	SQ YD	1657	1657
50300100	FLOOR DRAINS	EACH	28	28
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5.6	5.6
50300260	BRIDGE DECK GROOVING	SQ YD	2908	2908
50300300	PROTECTIVE COAT	SQ YD	<b>502</b>	<b>502</b>
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	840	840
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	320	320
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	107	107
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1175	1175
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1175	1175
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20	20
78300100	PAVEMENT MARKING REMOVAL	SQ FT	871	871
X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	3550	3550
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	444	444
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	3062	3062
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	3062	3062
Z0012130	BRIDGE DECK SCARIFICATION (3/4 INCH)	SQ YD	3062	3062
Z0015802	PLUG EXISTING DECK DRAINS	EACH	28	28
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	4	4
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	335	335
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					72	D7 BRIDGE REPAIRS 2011-2	MACON	25	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 74487			
	PLOT DATE = #DATE#	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							