

PAVEMENT MARKING SCHEDULE		URETHANE PAVEMENT MARKING - LINE 4"	URETHANE PAVEMENT MARKING - LINE 6"	PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
STATION TO STATION		FOOT	FOOT	SQ FT	FOOT	SQ FT	EACH
EB							
318+75.00	TO 319+00.00	50.0	6.3	0.0	4.5	1.5	0.0
319+00.00	TO 321+42.00	484.0	60.5	136.0	43.6	14.5	0.0
321+42.00	TO 324+88.99	694.0	86.7	231.3	62.5	20.8	10.0
324+88.99	TO 329+00.00	822.0	102.8	125.0	74.0	24.7	0.0
WB							
321+00.00	TO 322+35.38	270.8	33.8	74.3	24.4	8.1	0.0
322+35.38	TO 325+82.37	694.0	86.7	231.3	62.5	20.8	10.0
325+82.37	TO 328+50.00	535.3	66.9	72.7	48.2	16.1	0.0
TOTALS		3550.0	444.0	871.0	320.0	107.0	20.0

TRAFFIC CONTROL DEVICES SCHEDULE		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
STATION TO STATION		FOOT	FOOT	SQ FT	FOOT
STAGE I					
EB	319+26.00 TO 321+00.00	175.0	0.0	1.0	0.0
EB	321+00.00 TO 325+12.50	412.5	0.0	0.0	0.0
WB	322+12.50 TO 326+25.00	412.5	0.0	0.0	0.0
WB	326+25.00 TO 328+00.00	175.0	0.0	1.0	0.0
STAGE II					
EB	319+26.00 TO 321+00.00	0.0	175.0	0.0	1.0
EB	321+00.00 TO 325+12.50	0.0	412.5	0.0	0.0
WB	322+12.50 TO 326+25.00	0.0	412.5	0.0	0.0
WB	326+25.00 TO 328+00.00	0.0	175.0	0.0	1.0
TOTALS		1175.0	1175.0	2.0	2.0

WIDENING SCHEDULE		SUBBASE GRANULAR MATERIAL, TYPE B	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	PAVEMENT FABRIC	PAVED SHOULDER REMOVAL
STATION TO STATION		TON	SQ YD	SQ YD	SQ YD
EB					
318+75.00	TO 319+00.00	1.9	16.7	16.7	16.7
319+00.00	TO 321+42.00	36.7	322.7	322.7	322.7
321+42.00	TO 324+88.99	0.0	0.0	0.0	0.0
324+88.99	TO 329+00.00	41.5	364.7	364.7	265.7
		0.0			
WB		0.0			
321+00.00	TO 322+35.38	20.5	180.3	180.3	180.3
322+35.38	TO 325+82.37	0.0	0.0	0.0	0.0
325+82.37	TO 328+50.00	21.3	186.8	186.8	186.8
TOTALS		122.0	1071.0	1071.0	972.0

FILE NAME =
c:\p\work\p\dot\swartzr\08289400\477

USER NAME = swartzr
487-sht-sch.dgn
PLOT SCALE = 50.0000 ' / IN.
PLOT DATE = 2/7/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	D7 BRIDGE REPAIRS 2011-2	MACON	25	5
CONTRACT NO. 74487				
ILLINOIS FED. AID PROJECT				