

PAVING SCHEDULE			LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	LEVELING BINDER (MACHINE METHOD), N70	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	INCIDENTAL HOT-MIX ASPHALT SURFACING
LOCATION														
STATION	TO	STATION	FOOT	FOOT	SQ FT	SQ YD	GALLON	TON	TON	TON	TON	SQ YD	SQ YD	
462+00.00	TO	462+35.00	35.0	22.0	85.6	0.0	8.6	0.2	7.2	1.8	1.3	85.6	12.2	
462+35.00	TO	485+74.00	2339.0	22.0	5717.6	5717.6	571.8	11.4	480.3	240.1	173.6	0.0	0.0	
485+74.00	TO	486+09.00	35.0	22.0	85.6	0.0	8.6	0.2	7.2	1.8	2.7	85.6	12.2	
486+09.00	TO	486+45.00	36.0	22.0	88.0	0.0	0.0	0.0	0.0	0.0	2.7	0.0	0.0	
486+45.00	TO	486+80.00	35.0	22.0	85.6	0.0	8.6	0.2	7.2	1.8	2.7	85.6	12.2	
486+80.00	TO	518+72.00	3192.0	22.0	7802.7	7802.7	780.3	15.6	655.4	327.7	200.5	0.0	0.0	
518+72.00	TO	519+07.00	35.0	22.0	85.6	0.0	8.6	0.2	7.2	1.8	1.3	85.6	12.2	
519+07.00	TO	575+00.00	NA	22.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
575+00.00	TO	575+35.00	35.0	22.0	85.6	0.0	8.6	0.2	7.2	1.8	1.3	85.6	12.2	
575+35.00	TO	618+30.00	4295.0	22.0	10498.9	10498.9	1049.9	21.0	881.9	441.0	298.8	0.0	0.0	
618+30.00	TO	618+92.00	62.0	22.0	151.6	151.6	17.9	0.4	15.0	6.4	2.4	0.0	0.0	
618+92.00	TO	619+14.00	22.0	22.0	53.8	53.8	7.3	0.1	6.2	2.3	0.0	0.0	0.0	
619+14.00	TO	619+49.00	35.0	22.0	85.6	0.0	11.7	0.2	9.8	1.8	1.3	85.6	16.7	
TOTALS			10156.0		24826.0	24224.0	2482.0	50.0	2085.0	1028.0	689.0	513.0	78.0	

SEE ENTRANCE SCHEDULE