

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES, LOCATION DESCRIPTION, SUMMARY OF QUANTITIES
3-5	SUBSTRUCTURE SEALING PLANS
6-9	EXISTING STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 9.

STANDARD 701001-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701006-03	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701201-04	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701901-01	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

PROJECT LOCATION

PROJECT LOCATION

ROUTE: FAS 1807
 MARKED: Business US 50
 SECTION: 1B-1
 STATION: 29+99.84
 STRUCTURE NUMBERS: 051-0053

TYPE OF BRIDGE: Welded Plate Girders (6 Girders Total, River Span)
 LOCATION: 0.5 Miles East of Lawrenceville
 FEATURE CARRIED/SPANNED: Business US 50 over the Embarrass River

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT STRUCTURE NUMBER 051-0053 ON US BUSINESS 50 IN LAWRENCE COUNTY.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING THE BEAM ENDS, LATERAL BRACES, AND BEARINGS AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS. THE WORK ALSO INCLUDES CLEANING AND SEALING THE CONCRETE SUBSTRUCTURE UNITS OF THE BRIDGE AT LOCATIONS AS SHOWN IN THE PLANS.

100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		0014
58700300	CONCRETE SEALER	SQ FT	670	670
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
Z0007114	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES	L SUM	1	1
Z0010400	CLEANING BRIDGE SEATS	SQ FT	670	670
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1

• D7 BRIDGE PAINTING 2011-3

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES LOCATION DESCRIPTION & SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pw_work\p\dot\swartzw\d0262716\d774	528-shr-index.dgn	DRAWN -	REVISED -			1807	*	LAWRENCE	9	2
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -				CONTRACT NO. 74520				
PLOT DATE = 4/5/2011	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				
				SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.			