

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ACRRI		
				0004 L-01 90% FED. 10% STATE	0011 LIC 90% FED. 10% STATE	0040 LIC 90% FED. 10% STATE
X5210490	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 2000K	EACH	20		20	
X5210180	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 550K	EACH	20		20	
X5210255	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 1700K	EACH	20		20	
87001300	ELECTRIC CABLE IN TRENCH, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	14,470	14,470		
83009210	LIGHT POLE, ALUMINUM, 45 FT. M.H., 2-6 FT. MAST ARMS	EACH	10	10		
X0327277	RELOCATE KIOSK	EACH	1	1		
Z0023902	REMOVE PRESSURE RELIEF WELL	EACH	1	1		
X0327276	STAGED VEHICLE DETECTION AND SURVEILLANCE	L SUM	1	1		
20100500	TREE REMOVAL, ACRES	ACRE	17.75	17.75		
20200100	EARTH EXCAVATION	CU YD	248470	248470		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10237	10237		
20400800	FURNISHED EXCAVATION	CU YD	307140	307140		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	10237	10237		
20800150	TRENCH BACKFILL	CU YD	2605	2605		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	15356	15356		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	170130	170130		
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	15375	15375		
21501052	EXPLORATION TRENCH 32" DEPTH	FOOT	20000	20000		
* 25000210	SEEDING, CLASS 2A	ACRE	30.75	30.75		
* 25000305	SEEDING, CLASS 3A	ACRE	18.75	18.75		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5091	5091		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5091	5091		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5091	5091		
* 25100115	MULCH, METHOD 2	ACRE	147.5	147.5		
* 25100630	EROSION CONTROL BLANKET	SQ YD	114236	114236		
* 25200200	SUPPLEMENTAL WATERING	UNIT	1800	1800		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11312	11312		
28000305	TEMPORARY DITCH CHECKS	FOOT	1060	1060		
28000400	PERIMETER EROSION BARRIER	FOOT	27589	27589		
28000500	INLET AND PIPE PROTECTION	EACH	58	58		
28000510	INLET FILTERS	EACH	32	32		

* SPECIALTY ITEM

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw\work\pwidot\owenbj\dms64842\0876491-500.dgn		DRAWN -	REVISED -			270	60-1B-1	MADISON	712	6	
PLOT SCALE = 50.00000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76A91					
PLOT DATE = 3/25/2011		DATE -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					