

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				ACTM 0004 LS1 90% FED 10% STATE	ACR1 0011 LIC 90% FED 10% STATE	ACR2 0040 LIC 90% FED 10% STATE
CODE NO	ITEM	UNIT				
51203200	TEST PILE METAL SHELLS	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
51602000	PERMANENT CASING	FOOT	2920		2920	
51603000	DRILLED SHAFT IN SOIL	CU YD	3058		3058	
51604000	DRILLED SHAFT IN ROCK	CU YD	388		388	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	240		240	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	160		160	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16			16
54003000	CONCRETE BOX CULVERTS	CU YD	135.2			135.2
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	7	7		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	35	35		
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	16	16		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	130	130		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	266	266		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1667	1667		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	766	766		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	768	768		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	123	123		
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	129	129		
550A1010	STORM SEWERS, CLASS A, TYPE 4 24"	FOOT	128	128		
55100900	STORM SEWER REMOVAL 18"	FOOT	145	145		
55101200	STORM SEWER REMOVAL 24"	FOOT	1048	1048		
55101600	STORM SEWER REMOVAL 36"	FOOT	69	69		
58700300	CONCRETE SEALER	SQ FT	3794		3794	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	527		527	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	36	36		
60107600	PIPE UNDERDRAINS 4"	FOOT	30500	30500		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1350	1350		
60200505	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 5 FRAME, OPEN LID	EACH	1	1		
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	2	2		

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -			270	60-1B-1	MADISON	712	9	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CONTRACT NO. 76A91					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.