

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		ACTM 0004 L1C 90% FED 10% STATE	ACBRI 0011 L1C 90% FED 10% STATE	ACBRI 0040 L1C 90% FED 10% STATE
60201310	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 20 FRAME AND GRATE	EACH	4	4		
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4		
60230000	INLETS, TYPE A, TYPE 2 GRATE	EACH	<del style="text-align: center;">1	<del style="text-align: center;">1		
60253800	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 8 GRATE	EACH	2	2		
60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAME AND GRATES	EACH	12	12		
60500050	REMOVING CATCH BASINS	EACH	4	4		
60615400	PAVED DITCH, TYPE A-15	FOOT	1120	1120		
60616150	PAVED DITCH, TYPE A-60	FOOT	105	105		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	21200	21200		
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3525	3525		
* 63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	200	200		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6		
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	6	6		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8		
63200310	GUARDRAIL REMOVAL	FOOT	24713	24713		
63200400	CABLE ROAD GUARD REMOVAL	FOOT	4508	4508		
63500105	DELINEATORS	EACH	112	112		
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	2761	2761		
63700805	CONCRETE BARRIER TRANSITION	FOOT	30	30		
63700900	CONCRETE BARRIER BASE	FOOT	2761	2761		
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	1800	1800		
64200105	SHOULDER RUMBLE STRIPS	FOOT	20705	20705		
66500105	WOVEN WIRE FENCE, 4'	FOOT	3165	3165		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	41	41		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7	7		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	5	5		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	42	42		
67100100	MOBILIZATION	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		

* SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -			270	60-1B-1	MADISON	712	10	
		CHECKED -	REVISED -			CONTRACT NO. 76A91					
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	